DISCUSSION OF SURFICIAL MATERIALS The unconsolidated deposits overlying bedrock in Connecticut range from a few feet to several hundred feet in thickness. These earth materials significantly affect human development of the land. Most of the unconsolidated materials are deposits of continental glaciers that covered all of New England at least twice during the Pleistocene ice age. These glacial deposits are divided into two broad categories, glacial till and glacial stratified deposits. Till, the most widespread glacial deposit, was laid down directly by glacier ice and is characterized by a nonsorted matrix of sand, silt, and clay with variable amounts of stones and large boulders. Glacial meltwater deposits are concentrated in both small and large valleys and were laid down by glacial meltwater in streams and lakes in front of the retreating ice margin during deglaciation. These deposits are characterized by layers of well-sorted to poorly sorted gravel, sand, silt, and clay. Postglacial sediments, primarily floodplain alluvium and swamp deposits, make up a lesser proportion of the unconsolidated materials of Connecticut. Alluvium is largely reworked from glacial materials and has similar physical characteristics. The distribution of surficial (unconsolidated) materials that lie between the land surface

(below the pedogenic soil) and the bedrock surface is shown on this map to the extent that it is known or can be inferred. The cross sections (figs. 1 and 2) and the block diagram (fig. 3) illustrate the characteristic vertical distribution of glacial till, glacial meltwater deposits, and postglacial deposits encountered in Connecticut. The areal distribution of till and stratified deposits is related to the physiographic regions of the State: the eastern and western highlands and the central lowland (fig. 4.) Cross section A-A' (fig. 1) transects the central lowland and extends into the bordering eastern and western highlands. In highland areas, till is the major unconsolidated material, present as a discontinuous mantle of variable thickness over the bedrock surface. Till is thickest in drumlins and on the northwest slopes of hills (shaded till areas on map). Glacial meltwater deposits that average 10-40 feet in thickness overlie the till in small upland valleys and commonly in north-sloping pockets between bedrock hills. In the central lowland, especially in the north half, glacial stratified deposits are the predominant surficial materials. These deposits generally overlie till; however, well logs indicate that in some places till is not present and the stratified deposits lie directly on bedrock. The extensive stratified deposits of the central lowland average 50-100 feet in thickness, and in the northern part they almost completely mask the till-draped bedrock surface. Postglacial materials locally overlie the glacial deposits throughout the State. Alluvium occurs on the floodplains of most streams and rivers. Swamp deposits occur in poorly drained areas. Talus occurs along the bases of steep bedrock cliffs, principally along the traprock ridges within the central lowland. Salt-marsh and estuarine deposits occur mainly along the tidal portions of streams and rivers entering Long Island Sound. Beach deposits occur along the shoreline of Long Island Sound. This map is a companion to the Quaternary Geologic Map of Connecticut (Stone and

Schafer, unpublished data). Till and postglacial deposits are shown similarly on both maps. Glacial stratified deposits are particularly emphasized on both maps. These sediments are the major ground-water aquifers in the State and are also the major sources of construction aggregate. On the Quaternary Geologic Map, the glacial stratified deposits are described in terms of depositional environments (fluvial or lacustrine) and depositional chronology. On this the Surficial Materials Map, the texture (grain-size distribution) of these deposits is shown. The units on this map delineate textural changes in the subsurface as well as areally at the surface. An earlier map at 1:125,000 scale of central Connecticut (Stone and others, 1979) shows only surface textural units; a separate map in the same series (Langer, 1979) shows subsurface deposits of fine-grained materials. Several previous 1:24,000-scale quadrangle maps in Connecticut show threedimensional textural units and refer to them as "superposed deposits" (see Stone, 1976 and Radway and Schanbel, 1976, as examples). On this map, the term "stack unit" (Kempton, 1981) is used in place of superposed deposits.

DISTRIBUTION OF TEXTURES IN GLACIAL MELTWATER DEPOSITS

The distribution of textural units is extrapolated from both point data (well and test-hole logs, gravel pits, and shovel holes) and from interpretation of landforms based on the principles of morphosequence deposition and systematic northward ice retreat (Koteff, 1974; Koteff and Pessl, 1981). These concepts provide a model by which grain-size distribution can be predicted from the morphology of a deposit, given primary data about the textures at specific points. A morphosequence is a package of sediments deposited contemporaneously by meltwater flowing from the glacier margin to a specific base level. Within a morphosequence, grain size decreases and sorting improves from the icemarginal (proximal) end of a deposit downstream to the distal end. Landforms are ansitional within a sequence as well, ranging from ice-contact forms (eskers, kettles, kames) at the head (proximal end) of a deposit to uncollapsed forms (delta-foreset slopes, lake-bottom plains, valley trains) downstream (distal end). Coarser grained sediments are associated with the proximal parts of morphosequences, finer grained sediments are associated with distal parts; given this principle, textural distribution can be mapped using

point data that serve as controls. The relationship between textural variations and morphosequences is illustrated by cross section B-B' (fig. 2), which shows the distribution of texture units in the northern Quinnipiac River valley. This north-south section transects seven chronologically numbered morphosequences. Dashed lines drawn to the six southern sequences represent the probable generalized surface gradients of the heads of these deposits, prior to collapse (due to melting of buried ice) and subsequent stream entrenchment. From north to south within each of these sequences, the textures grade from coarse- to fine-grained sediments and the topography changes from collapsed to non-collapsed landforms. The longitudinal and vertical relationships illustrated by this section are common in other valleys as well. Stack units similar to those on cross section B-B' (fig. 2) occur throughout the stratified deposits of Connecticut. Many deposits having similar superposition of materials of differing texture were produced by geologic processes that occurred repeatedly in time and space during the deglaciation of Connecticut. For example, the sg/s/f and s/f stack units commonly occur in glacial-lake deltas. Morphosequences 1 through 6 on section B-B' are in fact a series of ice-marginal deltas. The sg/f stack unit commonly results from fluvial meltwater (or postglacial stream) terrace deposition on slightly older lake bottom deposits, as in sequence 7 on section B-B'. The f/sg and s/sg units commonly occur in the distal parts of morphosequences where the sand or fines overlap the collapsed, coarser, proximal parts of other (older) sequences. Examples of this are found in the distal parts of sequences 4 and 7. Many basic texture units (g, sg, s, f) likewise have broadly common origins. Units of gravel or sand and gravel often occur in the proximal parts of deposits, or were commonly laid down in glaciofluvial environments. Units of sand and fine-grained sediment are typically associated with distal parts of sequences and were usually laid down in lacustrine environments.

THICKNESS OF MATERIALS

The thickness of surficial materials in Connecticut varies considerably because of such

factors as the high relief of the bedrock surface, changing conditions of deposition during deglaciation, and various effects of postglacial erosion and removal of glacial sediments. The point data shown on the map are modified logs of wells and test holes (see fig. 5) that provide information about thicknesses. In thick till areas, most of the available point data are shown. Depths to bedrock given in the logs from till areas are shown on the map as the thickness of till, although in some places lenses of sand and gravel may be present within or at the base of till. Various log descriptions were interpreted as till; for example, the term "hardpan" was generally interpreted as till, but in some places, it may represent coarse, stony gravel. In glacial stratified deposits, the point data shown may have been selected from numerous logs to show representative thicknesses of materials both in single units and in individual textural components of stack units; in some areas the logs shown may be the only ones available. The point data are not uniformly distributed across the State. Some logs may describe a textural stacking that is more detailed than or in disagreement with, the map unit. Typical situations where this may occur are explained below and examples are located on the map view of the block diagram (fig. 3). In areas where coarser material overlies finer material, for example units sg/s and sg/f, the upper coarse material is commonly absent in places where later stream erosion has taken place (fig. 3, locality 1) or on steep frontal slopes of deltas (fig. 3, locality 2); the details of these areas are too small to show at the scale of this map. Point data from these places will indicate only sand or fines. Some point data indicate a thickness of sand and gravel or gravel at the base of the section, but this information is not reflected in the map unit (fig. 2 and fig. 3, locality 3). This situation arises because the distribution of coarse-grained material in the subsurface is more patchy and harder to map than subsurface fine-grained materials. Where the point data are adequate, units such as f/sg and s/sg are shown on the map; otherwise, scattered points indicate the presence of unmapped bodies of coarse-grained material in the subsurface. Some points located in areas shown as sand and gravel (sg) on the map indicate a more detailed textural stacking of small bodies of sand or fines within the coarser materials (fig. 3, locality 4). The block diagram (fig. 3) illustrates that the general location of the thickest stratified materials is in the middle of valleys (except where they have been removed by postglacial

EXPLANATION OF MAP SYMBOLS

erosion along modern streams) and that these deposits thin toward the valley sides.

Point data—Thickness (in feet) and texture of surficial materials from logs of test holes and wells. Sources of logs are indexed in figure 5. Logs have been generalized by combining thin units, and translated into the letter symbols used for map units. For more detailed information, please see Description of Map Units on this sheet.

- Alluvium sw Swamp deposits
- sm Salt-marsh deposits g Gravel
- rk Bedrock
- rs Rotten rock (weathered bedrock) Refusal (may represent surface of bedrock, large boulder, stony till, or coarse gravel)
- REFERENCES Deane, R.E., 1967, The surficial geology of the Hartford South quadrangle, with map: Connecticut Geological and Natural History Survey Quadrangle Report 20, 43 p.

Haeni, F.P., and Anderson, H.R., 1980, Hydrogeologic data for south-central Connecticut: Connecticut Water Resources Bulletin 32, 43 p. Kempton, J.P., 1981, Three-dimensional geologic mapping for environmental studies in Illinois: Illinois Geological Survey Environmental Geology Note 100, 43 p. Koteff, Carl, 1974, The morphologic sequence concept and deglaciation of southern New England, in Coates, D.R., ed., Glacial geomorphology: Binghamton, N.Y., State University of New York, Publications in Geomorphology, p. 121-144. Koteff, Carl, and Pessl, Fred, Jr., 1981, Systematic ice retreat in New England: U.S.

Geological Survey Professional Paper 1179, 20 p. Langer, W.H., 1979, Map showing distribution and thickness of the principal fine-grained deposits, Connecticut Valley urban area, central New England: U.S. Geological Survey Miscellaneous Investigations Series Map I-1074-C, scale 1:125,000. Mazzaferro, D.L., 1973, Hydrogeologic data for the Quinnipiac River basin, Connecticut: Connecticut Water Resources Bulletin 26, 54 p. Pessl, Fred, Jr., and Schafer, J.P., 1968, Two-till problem in Naugatuck-Torrington area, western Connecticut, in Orville, P.M., ed., New England Intercollegiate Geological

book for fieldtrips in Connecticut: Connecticut Geological and Natural History Survey Guidebook 2, Trip B-1, 25 p. Radway, J.A., and Schnabel, R.W., 1976, Map showing unconsolidated materials, Avon quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-514-C, scale 1:24,000.

Ryder, R.B., and Weiss, L.A., 1971, Hydrogeologic data for the Upper Connecticut River basin, Connecticut: Connecticut Water Resources Bulletin 26, 54 p. Stone, J.R., 1976, Map showing unconsolidated materials, Windsor Locks quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-450-E, Stone, J.R., London, E.H., and Langer, W.H., 1979, Map showing textures of

unconsolidated materials, Connecticut Valley urban area, central New England: U.S.

Conference 60th Annual Meeting, New Haven, Conn., Oct. 25-27, 1968, Guide-

Geological Survey Miscellaneous Investigations Series Map I-1074-B, scale Wentworth, C.K. 1922, A scale of grade and class terms for clastic sediments: Journal of Geology, v. 30, p. 377–392.

DESCRIPTION OF MAP UNITS GLACIAL ICE-LAID DEPOSITS Glacial ice-laid deposits (tills) consist of nonsorted, generally nonstratified mixtures of grain-sizes ranging from clay to large boulders. The matrix of most tills is composed dominantly of sand and silt. Boulders within and on the surface of tills range from sparse to abundant. Some tills contain lenses of sorted sand and gravel and, less commonly, masses of laminated fine-grained sediments. The color and lithology of till vary across Connecticut, but generally reflect the composition of the local underlying and northerly adjacent bedrock from which the till was derived (see fig. 4). Till blankets the bedrock surface in variable thickness, ranging from 0 to about 200 ft, and commonly underlies stratified meltwater deposits. Tills deposited during two separate glaciations occur in superposition within Connecticut (Pessl and Schafer, 1968). The upper till was deposited during the last (late Wisconsinan) glaciation; it is the most extensive till and is commonly observed in surface exposures, especially in areas where till thickness is less than 15 ft; it is described in the thin till unit description below. The lower till or "old" till was deposited during an earlier glaciation (probably Illinoian). The lower till has a more patchy distribution; it is principally a subsurface deposit, generally overlain by upper till, and therefore not shown as a separate map unit; the lower till does however constitute the bulk of material in the areas where till thickness is greater than 15 ft; it is described in the thick till unit description below. In all two-till exposures, the base of the upper till truncates the weathered surface of the old till. The lower part of the upper till commonly displays a zone of shearing, dislocation, and brecciation in which clasts of lower till are mixed and incorporated into the upper till. End moraine deposits occur principally in southeastern Connecticut. These deposits were laid down by ablation processes along active ice margins during retreat of the last (late-Wisconsinan) ice sheet.

Thin till—areas where till is generally less than 10–15 ft thick and including areas of bedrock outcrop where till is absent. Predominantly upper till; loose to moderately compact, generally sandy, commonly stony. Two facies are present in some places; a looser, coarser-grained ablation facies, melted out from supraglacial position; and a more compact finer-grained lodgement facies deposited subglacially. In general, both facies of upper till derived from the red Mesozoic sedimentary rocks of the central lowland of Connecticut are finer-grained, more compact, less stony and have eastern and western highlands.

2 0 2 4 6 8 10 MILES

CONTOUR INTERVAL 50 FEET

DATUM IS MEAN SEA LEVEL

Thick till-areas where till is greater than 10-15 ft thick and including drumlins in which till thickness commonly exceeds 100 ft (maximum recorded thickness is about 200 ft). Although upper till is the surface deposit, the lower till constitutes the bulk of the material in these areas. Lower till is moderately to very compact, and is commonly finer-grained and less stony than upper till. An oxidized zone, the lower part of a soil profile formed during a period of interglacial weathering, is generally present in the upper part of the lower till. This zone commonly shows closely-spaced joints that are stained with iron and manganese oxides.

nd moraine deposits—Composed predominantly of ablation facies sandy upper till; lenses of stratified sand and gravel occur locally within the till. Fines (very fine sand, silt, and clay)—Composed of well-sorted, thin layers Surface boulders on end moraine deposits are generally more numerous of alternating silt and clay, or thicker layers of very fine sand and silt. Very than on adjacent till surfaces; dense concentrations of boulders are fine sand commonly occurs at the surface and grades downward into present in some places. Deposits occur as free-standing hummocky landrhythmically bedded silt and clay varves (lake-bottom deposits) forms, commonly in elongate ridges that trend NNE - SSW, and range in thickness from 10 to 60 ft. GLACIAL MELTWATER DEPOSITS

deposits; selected point data indicate the thickness in feet of the textural unit. In other

places stack units (such as units sg/s/f or s/f) indicate changes of textural units in the

subsurface; selected point data in these areas indicate the thickness in feet of each textural

unit in the section. Common depositional environments for each textural unit are given

in parentheses after each unit description.

Glacial meltwater deposits (stratified deposits) consist of layers of well-sorted to poorly Gravel—Composed mainly of gravel-sized particles; cobbles and boulders sorted gravel, sand, silt, and clay laid down by flowing meltwater in glacial lakes and predominate; minor amounts of sand within gravel beds, and sand streams which occupied the valleys and lowlands of Connecticut during retreat of the last comprises few separate layers. Gravel layers generally are poorly sorted ice sheet. Textural variations within the meltwater deposits occur both areally and and bedding commonly is distorted and faulted due to postdepositional vertically because meltwater-flow regimes were different in glaciofluvial (stream), glacollapse related to melting of ice. Gravel deposits are shown only where ciodeltaic (where a stream entered a lake), and glaciolacustrine (lake bottom) depositional observed in the field; additional gravel deposits may be expected, environments. Grain-size variations also resulted from meltwater deposition in positions either proximal to or distal from the retreating glacier margin, which was the principal delta-topset beds) sediment source. A common depositional scenario contained a proximal, ice-marginal meltwater stream in which horizontally bedded glaciofluvial gravel and/or sand and gravel were laid down; farther down valley, the stream entered a glacial lake where glaciodeltaic sediments were deposited consisting of horizontally layered sand and gravel delta-topset beds overlying inclined layers of sand in delta-foreset beds. Farther out in the glacial lake, glaciolacustrine very fine sand, silt, and clay settled out on the lake bottom in flat-lying, thinly bedded layers. Mappable textural variations are present in the vertical section of meltwater deposits in many places. This stacking of textural units commonly resulted from delta-topset beds) locally changing conditions of meltwater deposition. For example, glacial lakes drained upon ice retreat from particular positions. This may have been followed locally by distal glaciofluvial (stream) deposition from ice positions farther up valley. The resulting vertical section shows meltwater terrace sediments consisting of horizontally bedded fluvial sand and gravel which overlie lake-bottom sediments of very fine sand, silt and clay (shown as unit sg/f on the map). In other places glaciodeltaic deposition over an extended period windblown sediment) of time in a particular glacial lake caused deltaic deposits (sand and gravel topset beds over sand foreset beds, unit sg/s) to prograde farther out into the lake and to overlie lake-bottom sediments; such deposits are shown as stack unit sg/s/f on the map. Meltwater deposits are shown on this map as four basic units: gravel, sand and gravel, sand, and fines. Grain-size terminology used to define the textural range within these units is shown on the adjacent particle-size diagram. Stack units are also shown; these are combinations of the four basic units in various orders of superposition. The map units horizontally bedded, and overlies thicker, inclined layers of sand and described below show the texture of meltwater deposits through the total vertical section gravel (proximal deltaic deposits) to the extent that it is known or can be reasonably inferred. In some places only one Gravel overlying sand—Gravel is generally less than 20 ft thick, horizontextural unit (such as unit sg) describes the entire vertical thickness of the meltwater tally bedded, and overlies thicker, inclined layers of sand (proximal deltaic

principally in areas mapped as unit sg (proximal fluvial deposits or Sand and gravel—Composed of mixtures of gravel and sand within individual layers and as alternating layers. Sand and gravel layers generally range from 25 to 50 percent gravel particles and from 50 to 75 percent sand particles. Layers are well to poorly sorted; bedding may be distorted and faulted due to postdepositional collapse. It is likely that some deposits within this map unit actually are gravel or sand and gravel overlying sand. It is less likely that some of these deposits are sand (fluvial deposits or Sand—Composed mainly of very coarse to fine sand, commonly in wellsorted layers. Coarser layers may contain up to 25 percent gravel particles, generally granules and pebbles; finer layers may contain some very fine sand, silt, and clay (delta-foreset beds, very distal fluvial deposits, or Gravel overlying sand and gravel—Gravel is generally less than 20 ft thick,

(deltaic deposits)

Sand and gravel overlying sand—Sand and gravel is generally less that 20

ft thick, horizontally bedded, and overlies thicker, inclined layers of sand

Fine Deposits

Coarse Deposits

bottom deposits overlying slightly older collapsed proximal fluvial or deltaic deposits); in a few places sand or sand and gravel, generally less than 25 ft thick occurs on top of the f/sg unit and is indicated as s/f/sg and sg/f/sg on the map, respectively

Sand and gravel overlying sand overlying sand and gravel--Sand and Fines overlying sand—Fines of variable thickness, commonly in thinly bedded layers overlie sand of variable thickness (distal lake-bottom gravel is generally less than 20 ft thick, horizontally bedded, and overlies deposits overlying slightly older more delta-proximal lacustrine sediment) thicker inclined layers of sand; thickness of sand and gravel at the base of the section is variable (deltaic deposits overlying slightly older, more Sand overlying gravel—Sand of variable thickness overlies gravel of vari-POSTGLACIAL DEPOSITS

able thickness (younger distal deltaic or fluvial sediments overlying older, more proximal fluvial or deltaic sediments) Floodplain alluvium—Sand, gravel, silt, and some organic material, on the Sand overlying sand and gravel—Sand of variable thickness overlies sand floodplains of modern streams. The texture of alluvium commonly varies and gravel of variable thickness (distal deltaic or fluvial sediments overlyover short distances both laterally and vertically, and is often similar to the ing slightly older proximal fluvial or deltaic sediments) texture of adjacent glacial deposits. Along smaller streams, alluvium is commonly less than 5 ft thick. The most extensive deposit of alluvium on the map is along the Connecticut River where the texture is predominantly fine to very fine sand and silt; here and along other larger rivers, it may be Stacked Coarse Deposits Overlying Fine Deposits as much as 25 ft thick. Alluvium typically overlies thicker glacial stratified deposits, the general texture of which is indicated by various line patterns. ravel overlying sand overlying fines—Gravel is generally less than 20 ft

thick, horizontally bedded and overlies thicker inclined beds of sand which Alluvium overlying undifferentiated coarse deposits in turn overlie fines of variable thickness (proximal deltaic deposits overlying lake-bottom sediments) Alluvium overlying sand Gravel overlying fines—Gravel is generally less than 20 ft thick, horizontally bedded and overlies thicker thinly bedded fines (proximal fluvial Alluvium overlying fines deposits overlying lake-bottom sediments) Sand and gravel overlying sand overlying fines—Sand and gravel is generally less than 20 ft thick, horizontally bedded and overlies thicker inclined beds of sand which in turn overlie thinly bedded fines of variable thickness (deltaic deposits overlying lake-bottom sediment) Sand and gravel overlying fines—Sand and gravel is generally less than 20 ft thick, horizontally bedded and overlies thicker thinly bedded fines (fluvial meltwater terrace deposits overlying lake-bottom sediment)

less than about 10 ft thick; they are shown on the map only where they are Sand overlying fines—Sand is of variable thickness, commonly in inclined more than about 25 acres in area. Swamp deposits are underlain by foreset beds and overlies thinly bedded fines of variable thickness (distal glacial deposits or bedrock. They are often underlain by glacial till even deltaic deposits overlying lake-bottom sediment) where they occur within glacial meltwater deposits. Where swamp deposits are known or interred to be underlain by sand and/or lines, they are shown on the map by various line patterns Stacked Fine Deposits Overlying Coarse Deposits Swamp deposits overlying sand nes overlying sand and gravel—Fines of variable thickness, commonly in Swamp deposits overlying fines thinly bedded layers overlie sand and gravel of variable thickness (lake-

Swamp deposits overlying sand overlying fines

Swamp deposits overlying fines overlying sand

sm Salt-marsh and tidal-marsh deposits—Peat and muck interbedded with sand and silt, deposited in environments of low wave energy along the coast and in river estuaries. Marsh deposits are dominantly peat and muck, generally a few feet to 35 ft thick; they are shown on the map only where greater than about 25 acres in area. In the major estuaries marsh deposits may overlie estuarine deposits which are sand and silt with minor organic material as much as 40 - 90 ft thick. These deposits are generally underlain by the glacial material shown adjacent on the map; either till or sand and gravel. Where they are known or inferred to be underlain by sand or fines, they are shown on the map by various line patterns

and rarely more than a few feet thick. Many sand beaches along the

Boulders Cobbles Pebbles Granules Coarse sand Coarse sand Silt Clay

Grain-size classification used in this report (modified from Wentworth, 1922)

Salt-marsh and tidal-marsh deposits overlying sand Salt-marsh and tidal-marsh deposits overlying fines

Talus—Loose, angular blocks (mostly boulders) accumulated by rockfall at the bases of steep bedrock cliffs. Talus forms steep unstable slopes and is generally less than 10 ft thick. It occurs most extensively along the linear basalt and diabase ridges within the central lowland. Beach deposits—Sand and gravel deposited along the shoreline by waves and currents and by wind action. The texture of beach deposits varies over short distances and is generally controlled by the texture of nearby glacial materials exposed to wave action. Beach deposits are generally well sorted

Alluvium overlying undifferentiated coarse deposits overlying fine Connecticut coast have been "restored"; these have not been distinguished from natural beaches on this map; however, extensive beaches that consist totally of "made-land" are mapped as artificial fill Alluvium overlying undifferentiated fine deposits overlying coarse Artificial fill—Earth materials and manmade materials that have been artificially emplaced. Artificial fill is common throughout the map area but Swamp deposits—Muck and peat that contain minor amounts of sand, silt, has been shown on this map only where extensive areas of "made land" and clay, accumulated in poorly drained areas. Most swamp deposits are occur, principally along the coast.


PARTICLE DIAMETER 10 2.5 .16 .08 .04 .02 .01 .005 .0025 .00015 ii 256 64 4 2 1 .5 .25 .125 .068 .004 mr


GRAVEL PARTICLES

SURFICIAL MATERIALS MAP OF CONNECTICUT

25,000-foot grid based on Connecticut coordinate system

SAND PARTICLES FINE PARTICLES








Figure 4.—Generalized bedrock lithologic map of Connecticut. The color and composition of glacial (surficial) materials is a result of the lithologic characteristics of subjacent and northerly adjacent rock types. Arrows indicate direction of glacial-ice movement across the State (see Discussion of Mineral Composition of Surficial Materials).

SURFICIAL MATERIALS

Exaggeration of the vertical scale in relation to the horizontal scale causes slopes to appear steeper and deposits to appear thicker.

The true dip of interbedded basalts and sedimentary rocks west of center on the section is $10^{\circ}-20^{\circ}$.

DISCUSSION OF MINERAL COMPOSITION OF The character of the surficial materials of Connecticut is very much determined by the physical characteristics and mineral composition of the source rocks. This is conspicuously true of glacial deposits, and also of alluvium and stream-terrace deposits, which are largely derived from nearby glacial deposits. The relationship holds not only in areas directly underlain by specific rocks, but also "downstream" in the direction the glacier was moving. The directions of movement were south to southeast in most of Connecticut, but southwest to nearly west on the west side of the Connecticut Valley glacier lobe, as is shown by the arrows on the map. Abundant fragments of a particular rock generally occur no more than a few miles downstream from the source area, but scattered fragments, particularly of hard rocks, may occur tens of miles away. In the Glastonbury area of central Connecticut, till that is largely derived from Jurassic sedimentary rocks was deposited 0.2-1.0 mi downstream on metamorphic rocks (Langer, 1977). Fragments of distinctive rock types downstream from restricted source areas form indicator fans, two of which are shown in figure 4. The indicator fan in western Connecticut is derived from the sedimentary and igneous rocks of the Pomperaug Valley; the fan in southeastern Connecticut is derived from the Preston Gabbro. The following comments about the effects of specific rocks are based mostly on general impressions rather than detailed studies. These comments apply most strongly to glacial tills; the removal of fine particles from glacial and alluvial sands and gravels diminishes some of the contrasts in texture and color. The sedimentary rocks of central Connecticut produce surficial deposits that are commonly reddish brown; siltstones contribute considerable fine-grained material; and conglomerates contribute rounded pebbles and cobbles that have been broken out of matrix. Basalt and dolerite are relatively hard rocks; fragments are abundant near the sources, and occur mainly in the reddish-brown deposits derived from the adjacent

sedimentary rocks.

Deposits derived from quartzites contain abundant quartz sand grains and quartzite fragments. Quartzites, because of their hardness, occur as very widespread erratic fragments. Marbles produce fine-grained, light-colored, highly calcareous glacial deposits. Dark schists and phyllites (Walloomsac and Wepawaug) produce fine-grained, darkcolored deposits. Abundant flakes of muscovite are very conspicuous in deposits derived from muscovite schists. The weathering of iron sulfides in sulfidic schists and gneisses produces very rusty or iron-cemented deposits. Granitic rocks that are low in dark minerals produce light-colored deposits, with abundant quartz and feldspar in the sand and coarse silt sizes. Dark mafic and ultramafic rocks produce dark-colored deposits that contain abundant dark iron minerals. The undivided light-gray to medium-gray schists and gneisses underlie more than half of Connecticut; they are the source rocks for the widespread sandy-silty tills of various shades of light and medium gray and yellowish gray. Associated sands and gravels are generally yellowish to light brownish gray. These common deposits show considerable range of composition, color and texture, but lack the distinctive lithologic effects produced by the other rock types mentioned above.

REFERENCES Langer, W.H., 1977, Surficial geologic map of the Glastonbury quadrangle, Hartford and Middlesex Counties, Connecticut: U. S. Geological Survey Geologic Quadrangle Rodgers, John, (compiler) 1985, Bedrock geological map of Connecticut: Hartford,

Conn., Connecticut Geological and Natural History Survey.

EXPLANATION Most of the geologic contacts on this map and all the rock names and ages in the

explanation are derived from the Bedrock Geological Map of Connecticut at 1:125,000

other types, in bodies too small or too poorly known to show on the map. The lithologic

canics (Ordovician); in southeastern Connecticut, Preston Gabbro

asedimentary and metaigneous; wide variety of aluminous, felsic, inter-

- Boundary of coastal area where bedrock outcrops are rare or absent and

Undivided schists and gneisses—Mostly light-gray to medium-gray; met-

----- Margin of indicator fan composed of fragments of distinctive rock type

Generalized direction of ice movement, based on orientation of bedrock

mediate and mafic rocks (Devonian to Proterozoic)

(Ordovician)

Contact between bedrock lithologic units

striations and drumlins

lithologic units are not known



Sedimentary bedrock

EXPLANATION OF CROSS-SECTION VIEW

Sand deposits

Sand and gravel deposits

Sedimentary bedrock

Sand and gravel deposits

Sand and gravel overlying sand

Sand overlying sand and gravel

 $\frac{sg}{f}$ Sand and gravel overlying fines

Figure 3.—Block diagram illustrating the relationship of map units (shown on the surface view) to the subsurface distribution of

materials over the bedrock surface (shown on the cross-section view). Conditions at numbered localities are described in the map

Sand and gravel overlying sand overlying fines

f Fine deposits

Gravel overlying sand

Sand overlying fines

Fines overlying sand and gravel

Alluvium overlying fines

Till and bedrock

EXPLANATION OF SURFACE VIEW

Figure 5.—Index map to sources of point data in Connecticut. References are in accompanying list. Quadrangles boundaries are shown in red. For quadrangle names, see figure 6.

0 10 20 30 40 KILOMETERS

0 10 20 30 MILES

SOURCES OF POINT DATA IN CONNECTICUT

Baker, J.A., 1966, Records and logs of selected wells and test borings, ground-water levels in selected observation wells, and freshwater inflow into the Connecticut River at the CANEL site, Middletown, Connecticut: Connecticut Water Resources Bulletin Bingham, J.W., Paine, F.D., and Weiss, L.A., 1975, Hydrogeologic data for the lower Connecticut River basin, Connecticut: Connecticut Water Resources Bulletin 30, Cervione, M.A., Jr., Grossman, I.G., and Thomas, C.E., Jr., 1968, Hydrogeologic data for the lower Thames and southeastern coastal river basins, Connecticut: Connecticut Water Resources Bulletin 16, 65 p. Cervione, M.A., Jr., Mazzaferro, D.L., and Melvin, R.L., 1972, Water resources inventory

of Connecticut, part 6, Upper Housatonic River basin: Connecticut Water Resources Bulletin 21, 84 p. Grossman, I.G., and Wilson, W.E., 1970, Hydrogeologic data for the lower Housatonic River basin, Connecticut: Connecticut Water Resources Bulletin 20, 50 p. Haeni, F.P., 1978, Computer modeling of ground-water availability in the Pootatuck River valley, Newtown, Connecticut, with a section on quality of water by E.H. Handman: U.S. Geological Survey Water-Resources Investigations WRI 78-77, Haeni, F.P., and Anderson, H.R., 1980, Hydrogeologic data for south-central Connecticut: Connecticut Water Resources Bulletin 32, 43 p. Handman, E.H., Haeni, F.P., and Thomas, M.P., 1986, Water resources inventory of 29, 91 p. [Some editions may list Haeni as first author.]

Connecticut, part 9, Farmington River basin: Connecticut Water Resources Bulletin Hopkins, H.T., and Handman, E.H., 1975, Hydrogeologic data for the Farmington River basin, Connecticut: Connecticut Water Resources Bulletin 28, 49 p. Mazzaferro, D. L., 1973, Hydrogeologic data for the Quinnipiac River basin, Connecticut: Connecticut Water Resources Bulletin 26, 54 p. Mazzaferro, D.L., Handman, E.H., and Thomas, M.P., 1979, Water resources inventory of Connecticut, part 8, Quinnipiac River basin: Connecticut Water Resources Melvin, R.L., 1970, Hydrogeologic data for the upper Housatonic River basin, Connect-

icut: Connecticut Water Resources Bulletin 22, 33 p.

basins: Connecticut Water Resources Bulletin 15, 105 p. Thomas, C.E., Jr., Randall, A.D., and Thomas, M.P., 1966, Hydrogeologic data in the Quinebaug River basin, Connecticut: Connecticut Water Resources Bulletin 9, 84 p. Thomas, M.P., Bednar, G.A., Thomas, C.E., Jr., and Wilson, W.E., 1967, Water resources inventory of Connecticut, part 2, Shetucket River basin: Connecticut Water Resources Bulletin 11, 96 p. Thomas, M.P., Ryder, R.B., and Thomas, C.E., Jr., 1969, Hydrogeologic data for the southwestern coastal river basins, Connecticut: Connecticut Water Resources Bul-Weiss, L.A., Bingham, J.W., and Thomas, M.P., 1982, Water resources inventory of Connecticut, part 10, Lower Connecticut River basin: Connecticut Water Resources Bulletin 31, 85 p. Wilson, W.E., Burke, E.L., and Thomas, C.E., Jr., 1974, Water resources inventory of Connecticut, part 5, Lower Housatonic River basin: Connecticut Water Resources

——1974, Hydrogeology of southeastern Connecticut: Connecticut Office of State

inventory of Connecticut, part 1, Quinebaug River basin: Connecticut Water

resources inventory of Connecticut, part 4, Southwestern coastal river basins:

Connecticut, part 7, Upper Connecticut River basin: Connecticut Water Resources

Randall, A.D., Thomas, M.P., Thomas, C.E., Jr., and Baker, J.A., 1966, Water resources

Ryder, R.B., Cervione, M.A., Jr., Thomas, C.E., Jr. and Thomas, M.P., 1970, Water

Ryder, R.B., Thomas, M.P., and Weiss, L.A., 1981, Water resources inventory of

Ryder, R.B., and Weiss, L.A., 1971, Hydrogeologic data for the upper Connecticut River

Thomas, C.E., Jr., Bednar, G.A., Thomas, M.P., and Wilson, W.E., 1967, Hydrogeologic

Thomas, C.E., Jr., Cervione, M.A., Jr., and Grossman, I.G., 1968, Water resources

data for the Shetucket River basin, Connecticut: Connecticut Water Resources

inventory of Connecticut, part 3, Lower Thames and southeastern coastal river

basin, Connecticut: Connecticut Water Resources Bulletin 25, 54 p.

Planning, Map Report, 6 sheets.

Resources Bulletin 8, 102 p.

Bulletin 24, 78 p.


Bulletin 12, 48 p.

Bulletin 19, 79 p.

Connecticut Water Resources Bulletin 17, 54 p.

SURFICIAL MATERIALS MAP OF CONNECTICUT

Janet Radway Stone, John P. Schafer, Elizabeth Haley London, and Woodrow B. Thompson



Thompson, W.B., 1980, unpublished data.

Flint, R.F., 1968, The surficial geology of the Ansonia and Milford quadrangles, with maps: Connecticut Geological and Natural History Survey Quadrangle Report 23,

Schafer, J.P., 1968, Surficial geologic map of the Ashaway quadrangle, Connecticut-Rhode Island: U.S. Geological Survey Geologic Quadrangle Map GQ-712 ASHLEY FALLS

Massachusetts, Connecticut, and New York: U.S. Geological Survey Geologic

Holmes, G.W., and Newman, W.S., 1971, Surficial geologic map of the Ashley Falls quadrangle, Massachusetts-Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-936 Warren, C.R., and Harwood, D.S., 1978, Deglaciation ice fronts in the South Sandisfield and Ashley Falls quadrangles, Massachusetts and Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-1016.

Radway, J.A., and Schnabel, R.W., 1976, Map showing unconsolidated materials, Avon quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map Schnabel, R.W., 1962, Surficial geology of the Avon quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-147. Zen, E-An, and Hartshorn, J.H., 1966, Geologic map of the Bashbish Falls quadrangle,

Schafer, J.P., 1979, unpublished data.

London, E.H., 1984, Surficial geologic map of the Bethel quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-1519. Stone, J.R., and London, E.H., 1985, Surficial geologic map of the Botsford quadrangle,

Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-1524. Brown, C.E., 1974, Map showing unconsolidated materials, Branford quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-560-A. Flint, R.F., 1964, The surficial geology of the Branford quadrangle, with map: Connecticut Geological and Natural History Quadrangle Report 14, 45 p.

Thompson, W.B., 1980, unpublished data. Barker, R.M., 1984, unpublished data.

Quadrangle Map GQ-507.

Simpson, H.E., 1961, Surficial geology of the Bristol quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-145.

Colton, R.B., 1965, Geologic map of the Broad Brook quadrangle, Hartford and Tolland Counties, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-434. Langer, W.H., and Colton, R.B., 1973, Map showing unconsolidated materials, Broad Brook quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-451-B.

Flint, R.F., 1971, The surficial geology of the Guilford and Clinton quadrangles, with maps: Connecticut Geological and Natural History Survey Quadrangle Report 28,

COLCHESTER Stone, J.R., 1981, unpublished data.

Brown, C.E., and Colton, R.B., 1973, unpublished data. Colton, R.B., 1970, Preliminary surficial geologic map of the Collinsville quadrangle, Litchfield and Hartford Counties, Connecticut: U.S. Geological Survey Open-File COLUMBIA

Ziska, M.A., 1978, The surficial geology of the Columbia quadrangle: Storrs, Conn., University of Connecticut, unpublished M.S. thesis, 81 p. Warren, C.R., and Colton, R.B., 1974, Surficial geologic map of the Cornwall quadran-

gle, Litchfield County, Connecticut: U.S. Geological Survey Geologic Quadrangle

Thompson, Woodrow, 1975, Surficial geologic map of the Danbury quadrangle, Connecticut: U.S. Geological Survey Open-File Report 75-547. Randall, A.D., and Pessl, Fred, Jr., 1968, Surficial geologic map of the Danielson quadrangle, Windham County, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-660.

O'Leary, D.W., 1973, Map showing unconsolidated materials, Deep River quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-524-A. ——1977, Surficial geologic map of the Deep River quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-1370. Thompson, W.B., 1980, unpublished data.

Simpson, H.E., 1968, Surficial geologic map of the Durham quadrangle, Middlesex and New Haven Counties, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-756.

Pease, M.H., Jr., 1972, Geologic map of the Eastford quadrangle, Windham and Tolland Counties, Connecticut: U.S. Geological Survey Geologic Quadrangle Map EAST KILLINGLY London, E.H., and Melvin, R.L., 1980, unpublished data.

ELLINGTON Colton, R.B., 1972, Surficial geologic map of the Ellington quadrangle, Hartford and Tolland Counties, Connecticut: U.S. Geological Survey Geologic Quadrangle Map Koza, D.M., 1979, Map showing unconsolidated materials, Ellington quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-604-B.

Kelley, G.C., 1975, Surficial geologic maps of the Kent and Ellsworth quadrangles, Litchfield County, Connecticut: U.S. Geological Survey Open-File Report 75–171. -----1977, Late Pleistocene and Recent geology of the Housatonic River region in northwestern Connecticut: U.S. Geological Survey Open-File Report 77-545,

Flint, R.F., 1975, The surficial geology of the Essex and Old Lyme quadrangles, with maps: Connecticut Geological and Natural History Survey Quadrangle Report 31, Naylor, R.G., 1974, Map showing unconsolidated materials, Essex quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-587-A.

Pessl, Fred, Jr., 1966, Surficial geologic map of the Fitchville quadrangle, New London County, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-485. **GLASTONBURY** Langer, W.H., 1976, Map showing unconsolidated materials, Glastonbury quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-561-D. -----1977, Surficial geologic map of the Glastonbury quadrangle, Hartford and

Middlesex Counties, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-1354. Schafer, J.P., 1979, unpublished data.

Flint, R.F., 1971, The surficial geology of the Guilford and Clinton quadrangles, with maps: Connecticut Geological and Natural History Survey Quadrangle Report 28,

Flint, R.F., 1978, The surficial geology of the Haddam quadrangle, with map: Connecticut Geological and Natural History Survey Quadrangle Report 36, 27 p.

Barker, R.M., 1980, unpublished data.

Hildreth, C.T., and Colton, R.B., 1982, Surficial geologic map of the Hampden quadrangle, Massachusetts and Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-1544.

Dixon, H.R., and Pessl, Fred, Jr., 1966, Geologic map of the Hampton quadrangle, Windham County, Connecticut: U.S. Geological Survey Geologic Quadrangle Map HARTFORD NORTH

Cushman, R.V., 1963, Geology of the Hartford North quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-223. Pessl, Fred, Jr., and Hildreth, C.T., 1972, Unconsolidated materials, Hartford North quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Geologic Investigations Map I-784-A. HARTFORD SOUTH

Deane, R.E., 1967, The surficial geology of the Hartford South quadrangle, with map: Connecticut Geological and Natural History Survey Quadrangle Report 20, 43 p. Langer, W.H., Recny, C.J., and Koza, D.M., 1976, Map showing unconsolidated materials, Hartford South quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-487-F.

Stone, B.D., 1978, Surficial geologic map of the Jewett City quadrangle, New London

County, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-1434. Kelley, G.C., 1975, Surficial geologic maps of the Kent and Ellsworth quadrangles, Litchfield County, Connecticut: U.S. Geological Survey Open-File Report 75–171. -----1977, Late Pleistocene and Recent geology of the Housatonic River region in northwestern Connecticut: U.S. Geological Survey Open-File Report 77-545,

Warren, C.R., 1970, Surficial geologic map of the Litchfield quadrangle, Litchfield County, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-848.

MAMARONECK Schafer, J.P., 1979, unpublished data.

Stone, J.R., 1980, unpublished data.

Map MF-452-F.

Colton, R.B., 1965, Geologic map of the Manchester quadrangle, Hartford and Tolland Counties, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-433. Langer, W.H., and Recny, C.J., 1977, Map showing unconsolidated materials, Manchester quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies

MARLBOROUGH O'Leary, D.W., 1975, Map showing unconsolidated materials, Marlborough quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-645-A. ——1979, Surficial geologic map of the Marlborough quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-1504.

Hanshaw, P.M., 1962, Surficial geology of the Meriden quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-150. MIDDLE HADDAM

Deane, R.E., 1960, unpublished data. Tharin, J.C., 1973, unpublished data. London, E.H., and Stone, J.R., 1982, unpublished data.

Deane, R.E., 1957, unpublished data. London, E.H., 1982, unpublished data. Upson, J.E., 1970, unpublished data.

Flint, R.F., 1968, The surficial geology of the Ansonia and Milford quadrangles, with maps: Connecticut Geological and Natural History Survey Quadrangle Report 23,

Peper, J.D., 1976, Map showing unconsolidated materials, Monson quadrangle, Massachusetts-Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-734-A.

——1977, Surficial geologic map of the Monson quadrangle, Massachusetts and Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-1429. Goldsmith, Richard, 1962, Surficial geology of the Montville quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-148. ———1974, Map showing unconsolidated materials, Montville quadrangle, Connecticut:

U.S. Geological Survey Miscellaneous Field Studies Map MF-580-A. O'Leary, D.W., 1973, Map showing unconsolidated materials, Moodus quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-510-A. ——1975, Surficial geologic map of the Moodus quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-1205.

Flint, R.F., 1962, The surficial geology of the Mount Carmel quadrangle, with map: Connecticut Geological and Natural History Survey Quadrangle Report 12, 23 p. MOUNT KISCO Schafer, J.P., 1979, unpublished data.

Upson, J.E., 1971, Surficial geologic map of the Mystic quadrangle, Connecticut, New York, and Rhode Island: U.S. Geological Survey Geologic Quadrangle Map GQ-940.

Flint, R.F., 1978, The surficial geology of the Naugatuck quadrangle, with map: Connecticut Geological and Natural History Survey Quadrangle Report 35, 23 p. Langer, W.H., 1973, Map showing unconsolidated materials, New Britain quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-523-A. Simpson, H.E., 1959, Surficial geology of the New Britain quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-119.

NEW HARTFORD Schnabel, R.W., 1973, Map showing unconsolidated materials, New Hartford quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-542-A. ———1975, Geologic map of the New Hartford quadrangle, northwestern Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-1257.

Flint, R.F., 1965, The surficial geology of the New Haven and Woodmont quadrangles, with map: Connecticut Geological and Natural History Survey Quadrangle Report Recny, C.J., 1976, Map showing unconsolidated materials, New Haven and Woodmont

NEW LONDON Goldsmith, Richard, 1962, Surficial geology of the New London quadrangle, Connecticut-New York: U.S. Geological Survey Geologic Quadrangle Map GQ-176.

quadrangles, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map

Thompson, Woodrow, 1975, Surficial geologic map of the New Milford quadrangle, Connecticut: U.S. Geological Survey Open-File Report 75–548.

Colton, R.B., 1969, Surficial geologic map of the New Preston quadrangle, Litchfield County, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-782. Thompson, W.B., 1980, unpublished data.

Goldsmith, Richard, 1964, Surficial geology of the Niantic quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-329. ——1974, Map showing unconsolidated materials, Niantic quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-593-A.

Warren, C.R., 1972, Surficial geologic map of the Norfolk quadrangle, Litchfield County, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-983.

London, E.H., 1984, Surficial geologic map of the Norwalk North quadrangle, Connect-Malde, H.E., 1968, Surficial geologic map of the Norwalk South quadrangle, Fairfield Hanshaw, P.M., and Snyder, G.L., 1962, Surficial geology of the Norwich quadrangle, Flint, R.F., 1975, The surficial geology of the Essex and Old Lyme quadrangles, with Goldsmith, Richard, and Gaffney, J.W., 1974, unpublished data. Harwood, D.S., and Goldsmith, Richard, 1971, Surficial geologic map of the Oneco Barosh, P.J., 1980, unpublished data. Thompson, W.B., 1980, unpublished data. Schafer, J.P., 1979, unpublished data. Stone, B.D., and Randall, A.D., 1978, Surficial geologic map of the Plainfield quadrangle, Windham and New London Counties, Connecticut: U.S. Geological Survey Schafer, J.P., 1979, unpublished data. Fontaine, E.J., III, 1979, unpublished data. Colton, R.B., 1970, unpublished data. Malde, H.E., 1967, Surficial geologic map of the Roxbury quadrangle, Litchfield and New Haven Counties, Connecticut: U.S. Geological Survey Geologic Quadrangle

> Dixon, H.R., and Shaw, C.E., Jr., 1965, Geologic map of the Scotland quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-392.

Holmes, G.W., Newman, W.S., and Melvin, R.L., 1975, unpublished data. Thompson, W. B., 1980, unpublished data. SHERWOOD POINT Stone, J.R., and London, E.H., 1981, Surficial geologic map of the Westport and Sherwood Point quadrangles, Connecticut: U.S. Geological Survey Miscellaneous

Field Studies Map MF-1295. Moore, G.E., Jr., 1978, Preliminary bedrock, surficial, and structural data maps of the Southbridge quadrangle, Massachusetts and Connecticut: U.S. Geological Survey Open-File Report 78–220.

NORWALK NORTH

NORWALK SOUTH

County, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-718.

maps: Connecticut Geological and Natural History Survey Quadrangle Report 31,

quadrangle, Connecticut-Rhode Island: U.S. Geological Survey Geologic Quadran-

gle Map GQ-917.

Geologic Quadrangle Map GQ-1422.

icut: U.S. Geological Survey Miscellaneous Field Studies Map MF-1520.

Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-165.

Pessl, Fred, Jr., 1975, Surficial geologic map of the Southbury quadrangle, Fairfield and New Haven Counties, Connecticut: U.S. Geological Survey Open-File Report 75–172.

Holmes, G.W., Newman, W.S., and Melvin, R.L., 1970, Preliminary surficial geologic

map of the South Canaan quadrangle, Litchfield County, Connecticut: U.S

Geological Survey Open-File Map. Thompson, W.B., 1980, unpublished data. SOUTH COVENTRY Frankel, Larry, 1967, unpublished data.

Stone, J.R., 1982, unpublished data. La Sala, A.M., Jr., 1961, Surficial geology of the Southington quadrangle, Connecticut:

Geological Survey Miscellaneous Field Studies Map MF-1016.

U.S. Geological Survey Geologic Quadrangle Map GQ-146. SOUTH SANDISFIELD Harwood, D.S., 1979, Geologic map of the South Sandisfield quadrangle, Massachusetts and Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-1519. Warren, C. R., and Harwood, D. S., 1978, Deglaciation ice fronts in the South Sandisfield and Ashley Falls quadrangles, Massachusetts and Connecticut: U.S.

Schnabel, R.W., 1971, Surficial geologic map of the Southwick quadrangle, Massachusetts and Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-891. ——1974, Map showing unconsolidated materials, Southwick quadrangle, Massachusetts-Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-606-A.

SPRINGFIELD SOUTH Hartshorn, J.H., and Koteff, Carl, 1967, Geologic map of the Springfield South quadrangle, Hampden County, Massachusetts, and Hartford and Tolland Counties, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-678. Koteff, Carl, 1973, Map showing unconsolidated materials, Springfield South quadrangle, Massachusetts-Connecticut: U.S. Geological Survey Miscellaneous Field Studies

Map MF-509-A. Rahn, P.H., 1971, The surficial geology of the Spring Hill quadrangle, with map: Connecticut Geological and Natural History Survey Quadrangle Report 26, 31 p. STAFFORD SPRINGS

Pease, M.H., Jr., 1974, Map showing unconsolidated materials, Stafford Springs quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map ——1975, Surficial geologic map of the Stafford Springs quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-1216. **STAMFORD**

Schafer, J.P., 1979, unpublished data. Pessl, Fred, Jr., 1973, Map showing unconsolidated materials, Tariffville quadrangle, Connecticut-Massachusetts: U.S. Geological Survey Miscellaneous Field Studies Randall, A.D., 1970, Surficial geologic map of the Tariffville quadrangle, Connecticut-

Massachusetts: U.S. Geological Survey Geologic Quadrangle Map GQ-798. Warren, C.R., 1972, Surficial geologic map of the Thomaston quadrangle, Litchfield, New Haven, and Hartford Counties, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-984.

London, E.H., and Melvin, R.L., 1981, Reconnaissance map of surficial deposits in the Connecticut part of the Thompson quadrangle, Connecticut-Rhode Island: U.S. Geological Survey Open-File Report 81–1042.

TOLLAND CENTER Warren, C.R., 1978, unpublished data. **TORRINGTON** Colton, R.B., 1971, Surficial geologic map of the Torrington quadrangle, Litchfield and Hartford Counties, Connecticut: U.S. Geological Survey Geologic Quadrangle Map

GQ-939. Goldsmith, Richard, 1960, Surficial geology of the Uncasville quadrangle, Connecticut:

U.S. Geological Survey Geologic Quadrangle Map GQ-138. Feininger, Tomas, 1965, Surficial geologic map of the Voluntown quadrangle, Connecticut-Rhode Island: U.S. Geological Survey Geologic Quadrangle Map

Schafer, J.P., 1981, unpublished data. Porter, S.C., 1960, The surficial geology of the Wallingford quadrangle, with map: Connecticut Geological and Natural History Survey Quadrangle Report 10, 42 p.

Schafer, J.P., 1965, Surficial geologic map of the Watch Hill quadrangle, Rhode Island-Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-410. Schafer, J.P., 1982, unpublished data. Barosh, P.J., 1973, Preliminary surficial geologic map of the Webster quadrangle,

Massachusetts and Connecticut: U.S. Geological Survey Open-File Map. Peper, J.D., and Pease, M.H., Jr., 1975, Geologic map of the Westford quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-1214. WEST GRANVILLE Schnabel, R.W., 1973, Preliminary geologic map of the West Granville quadrangle,

Hampden County, Massachusetts, and Hartford County, Connecticut: U.S. Geological Survey Open-File Map. Stone, J.R., and London, E.H., 1981, Surficial geologic map of the Westport and Sherwood Point quadrangles, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-1295.

WEST SPRINGFIELD

Colton, R.B., and Hartshorn, J.H., 1971, Surficial geologic map of the West Springfield quadrangle, Massachusetts and Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-892. WEST TORRINGTON Colton, R.B., 1968, Surficial geologic map of the West Torrington quadrangle, Litchfield County, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-727.

Clebnik, S.M., 1974, Map showing unconsolidated materials, Willimantic quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-586-A. ——1980, The surficial geology of the Willimantic quadrangle, with map: Connecticut Geological and Natural History Survey Quadrangle Report 39, 45 p. WINDSOR LOCKS

Colton, R.B., 1960, Surficial geology of the Windsor Locks quadrangle, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-137. Stone, J.R., 1976, Map showing unconsolidated materials, Windsor Locks quadrangle, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map MF-450-E. Warren, C.R., 1970, Surficial geologic map of the Winsted quadrangle, Litchfield and

Hartford Counties, Connecticut: U.S. Geological Survey Geologic Quadrangle Map GQ-871. Pessl, Fred, Jr., 1970, Surficial geologic map of the Woodbury quadrangle, Litchfield and New Haven Counties, Connecticut: U.S. Geological Survey Geologic Quadrangle

Map GQ-896. Flint, R.F., 1965, The surficial geology of the New Haven and Woodmont quadrangles,

with map: Connecticut Geological and Natural History Survey Quadrangle Report Recny, C.J., 1976, Map showing unconsolidated materials, New Haven and Woodmont quadrangles, Connecticut: U.S. Geological Survey Miscellaneous Field Studies Map