



Dewberry®

PROJECT REPORT

For the

**U.S. Corp of Engineers High Resolution LiDAR Data Acquisition & Processing for
portions of Connecticut**

USACE Contract:

W912P9-10-D-0534

Task Order Number:

0002

Prepared for:

USDA Natural Resources Conservation Services

Prepared by:

Dewberry
8401 Arlington Boulevard
Fairfax, VA 22031-466

Report Date: August 9, 2012

Table of Contents

Executive Summary	3
1 Project Tiling Footprint.....	5
1.1 List of delivered tiles (1,742):	6
2 LiDAR Acquisition Report	17
2.1 PROJECT DESCRIPTION	17
2.2 MISSION PLANNING	17
2.3 ACQUISITION.....	19
2.4 PROCESSING.....	20
2.5 QA/QC	20
2.6 Final Deliverables	21
3 LiDAR Processing & Qualitative Assessment.....	21
3.1 Data Classification and Editing	21
3.2 Qualitative Assessment	23
3.3 Conclusion.....	25
4 Survey Vertical Accuracy Checkpoints	26
4.1 Survey Checkpoints not used in vertical accuracy testing.....	27
5 LiDAR Vertical Accuracy Statistics & Analysis	29
5.1 Background	29
5.2 Vertical Accuracy Test Procedures	29
5.3 Vertical Accuracy Testing Steps.....	30
5.4 Vertical Accuracy Results	31
5.5 Conclusion.....	32
6 Breakline Production & Qualitative Assessment Report	32
6.1 Breakline Production Methodology	32
6.2 Breakline Qualitative Assessment.....	33
6.3 Breakline Topology Rules	33
6.4 Breakline QA/QC Checklist	34
6.5 Data Dictionary.....	36
6.5.1 Horizontal and Vertical Datum.....	37
6.5.2 Coordinate System and Projection	37
6.5.3 Inland Streams and Rivers	37
Description.....	37
Table Definition.....	37

<i>Feature Definition</i>	37
6.5.4 <i>Inland Ponds and Lakes</i>	38
<i>Description</i>	38
<i>Table Definition</i>	38
<i>Feature Definition</i>	39
7 DEM Production & Qualitative Assessment.....	40
7.1 DEM Production Methodology.....	40
7.2 DEM Qualitative Assessment.....	41
7.3 DEM QA/QC Checklist.....	41

Executive Summary

The primary purpose of this project was to develop a consistent and accurate surface elevation dataset derived from high-accuracy Light Detection and Ranging (LiDAR) technology for use by USDA-NRCS Connecticut in such projects as conservation planning, floodplain mapping, dam safety assessments, and hydrologic modeling.

The LiDAR data were processed to a bare-earth digital elevation model (DEM). Detailed breaklines, bare-earth DEMs, and multiple LiDAR derivatives were produced for the project area. Data was formatted according to tiles with each tile covering an area of 1000 m by 1000 m. A total of 1,742 tiles were produced for the project encompassing an area of approximately 1,703 sq. kilometers.

The Project Team

Dewberry served as the prime contractor for the project. In addition to project management, Dewberry was responsible for LAS classification, all LiDAR products, breakline production, Digital Elevation Model (DEM) production, and quality assurance.

Dewberry's IES offices completed ground surveying for the project and delivered surveyed checkpoints. Their task was to acquire surveyed checkpoints for the project to use in independent testing of the vertical accuracy of the LiDAR-derived surface model. They also verified the GPS base station coordinates used during LiDAR data acquisition to ensure that the base station coordinates were accurate. Note that a separate Survey Report was created for this portion of the project.

Laser Mapping Specialist, Inc completed LiDAR data acquisition and data calibration for the project area.

Survey Area

The project area addressed by this report covers portions of the Connecticut counties of Litchfield and Fairfield.

The LiDAR aerial acquisition was conducted from December 13th, thru December 19th, 2011.

Datum Reference

Data produced for the project were delivered in the following reference system.

Horizontal Datum: The horizontal datum for the project is North American Datum of 1983 (NAD 83)

Vertical Datum: The Vertical datum for the project is North American Vertical Datum of 1988 (NAVD88)

Coordinate System: UTM Zone 18N

Units: Horizontal units are in meters, Vertical units are in meters.

Geoid Model: Geoid09 (Geoid 09 was used to convert ellipsoid heights to orthometric heights).

LiDAR Vertical Accuracy

For the Connecticut LiDAR Project, the tested $RMSE_z$ for open terrain checkpoints equaled **0.091 m** compared with the 0.0925 m specification; and the FVA computed using $RMSE_z \times 1.9600$ was equal to **0.179 m**, compared with the 0.185 m specification.

Project Deliverables

The deliverables for the project are listed below.

1. Classified Point Cloud LiDAR Data (Tiled)
2. Bare Earth LiDAR Data (Tiled)
3. First Return LiDAR Data (Tiled)
4. Last Return LiDAR Data (Tiled)
5. Model Key Point LiDAR Data (Tiled)
6. Bare Earth Surface (Raster DEM – ArcGrid Format)
7. Control & Accuracy Checkpoint Report & Points
8. Metadata
9. Project Report (Acquisition, Processing, QC)
10. Project Extents
11. Breakline Data (File GDB)
12. Intensity Imagery (GeoTIFF Format with 1m pixels)

1 Project Tiling Footprint

One thousand seven hundred and forty two (1,742) tiles were delivered for the project. Each tile's extent is 1000 meters by 1000 meters.




Figure 1: Project Map

1.1 List of delivered tiles (1,742):

18TXM2306	18TXM2424	18TXM2521	18TXM2611
18TXM2307	18TXM2425	18TXM2522	18TXM2612
18TXM2308	18TXM2426	18TXM2523	18TXM2613
18TXM2309	18TXM2427	18TXM2524	18TXM2614
18TXM2310	18TXM2428	18TXM2525	18TXM2615
18TXM2311	18TXM2429	18TXM2526	18TXM2616
18TXM2312	18TXM2430	18TXM2527	18TXM2617
18TXM2313	18TXM2431	18TXM2528	18TXM2618
18TXM2314	18TXM2432	18TXM2529	18TXM2619
18TXM2315	18TXM2433	18TXM2530	18TXM2620
18TXM2316	18TXM2434	18TXM2531	18TXM2621
18TXM2317	18TXM2435	18TXM2532	18TXM2622
18TXM2318	18TXM2436	18TXM2533	18TXM2623
18TXM2319	18TXM2437	18TXM2534	18TXM2624
18TXM2320	18TXM2438	18TXM2535	18TXM2625
18TXM2321	18TXM2439	18TXM2536	18TXM2626
18TXM2322	18TXM2440	18TXM2537	18TXM2627
18TXM2323	18TXM2441	18TXM2538	18TXM2628
18TXM2324	18TXM2442	18TXM2539	18TXM2629
18TXM2325	18TXM2443	18TXM2540	18TXM2630
18TXM2326	18TXM2444	18TXM2541	18TXM2631
18TXM2327	18TXM2445	18TXM2542	18TXM2632
18TXM2328	18TXM2446	18TXM2543	18TXM2633
18TXM2406	18TXM2447	18TXM2544	18TXM2634
18TXM2407	18TXM2448	18TXM2545	18TXM2635
18TXM2408	18TXM2449	18TXM2546	18TXM2636
18TXM2409	18TXM2506	18TXM2547	18TXM2637
18TXM2410	18TXM2507	18TXM2548	18TXM2638
18TXM2411	18TXM2508	18TXM2549	18TXM2639
18TXM2412	18TXM2509	18TXM2550	18TXM2640
18TXM2413	18TXM2510	18TXM2551	18TXM2641
18TXM2414	18TXM2511	18TXM2552	18TXM2642
18TXM2415	18TXM2512	18TXM2553	18TXM2643
18TXM2416	18TXM2513	18TXM2554	18TXM2644
18TXM2417	18TXM2514	18TXM2555	18TXM2645
18TXM2418	18TXM2515	18TXM2556	18TXM2646
18TXM2419	18TXM2516	18TXM2606	18TXM2647
18TXM2420	18TXM2517	18TXM2607	18TXM2648
18TXM2421	18TXM2518	18TXM2608	18TXM2649
18TXM2422	18TXM2519	18TXM2609	18TXM2650
18TXM2423	18TXM2520	18TXM2610	18TXM2651

18TXM2652	18TXM2744	18TXM2836	18TXM2928
18TXM2653	18TXM2745	18TXM2837	18TXM2929
18TXM2654	18TXM2746	18TXM2838	18TXM2930
18TXM2655	18TXM2747	18TXM2839	18TXM2931
18TXM2656	18TXM2748	18TXM2840	18TXM2932
18TXM2706	18TXM2749	18TXM2841	18TXM2933
18TXM2707	18TXM2750	18TXM2842	18TXM2934
18TXM2708	18TXM2751	18TXM2843	18TXM2935
18TXM2709	18TXM2752	18TXM2844	18TXM2936
18TXM2710	18TXM2753	18TXM2845	18TXM2937
18TXM2711	18TXM2754	18TXM2846	18TXM2938
18TXM2712	18TXM2755	18TXM2847	18TXM2939
18TXM2713	18TXM2756	18TXM2848	18TXM2940
18TXM2714	18TXM2806	18TXM2849	18TXM2941
18TXM2715	18TXM2807	18TXM2850	18TXM2942
18TXM2716	18TXM2808	18TXM2851	18TXM2943
18TXM2717	18TXM2809	18TXM2852	18TXM2944
18TXM2718	18TXM2810	18TXM2853	18TXM2945
18TXM2719	18TXM2811	18TXM2854	18TXM2946
18TXM2720	18TXM2812	18TXM2855	18TXM2947
18TXM2721	18TXM2813	18TXM2856	18TXM2948
18TXM2722	18TXM2814	18TXM2906	18TXM2949
18TXM2723	18TXM2815	18TXM2907	18TXM2950
18TXM2724	18TXM2816	18TXM2908	18TXM2951
18TXM2725	18TXM2817	18TXM2909	18TXM2952
18TXM2726	18TXM2818	18TXM2910	18TXM2953
18TXM2727	18TXM2819	18TXM2911	18TXM2954
18TXM2728	18TXM2820	18TXM2912	18TXM2955
18TXM2729	18TXM2821	18TXM2913	18TXM2956
18TXM2730	18TXM2822	18TXM2914	18TXM3006
18TXM2731	18TXM2823	18TXM2915	18TXM3007
18TXM2732	18TXM2824	18TXM2916	18TXM3008
18TXM2733	18TXM2825	18TXM2917	18TXM3009
18TXM2734	18TXM2826	18TXM2918	18TXM3010
18TXM2735	18TXM2827	18TXM2919	18TXM3011
18TXM2736	18TXM2828	18TXM2920	18TXM3012
18TXM2737	18TXM2829	18TXM2921	18TXM3013
18TXM2738	18TXM2830	18TXM2922	18TXM3014
18TXM2739	18TXM2831	18TXM2923	18TXM3015
18TXM2740	18TXM2832	18TXM2924	18TXM3016
18TXM2741	18TXM2833	18TXM2925	18TXM3017
18TXM2742	18TXM2834	18TXM2926	18TXM3018
18TXM2743	18TXM2835	18TXM2927	18TXM3019

18TXM3020	18TXM3112	18TXM3155	18TXM3247
18TXM3021	18TXM3113	18TXM3156	18TXM3248
18TXM3022	18TXM3114	18TXM3206	18TXM3249
18TXM3023	18TXM3115	18TXM3207	18TXM3250
18TXM3024	18TXM3116	18TXM3208	18TXM3251
18TXM3025	18TXM3117	18TXM3209	18TXM3252
18TXM3026	18TXM3118	18TXM3210	18TXM3253
18TXM3027	18TXM3119	18TXM3211	18TXM3254
18TXM3028	18TXM3120	18TXM3212	18TXM3255
18TXM3029	18TXM3121	18TXM3213	18TXM3256
18TXM3030	18TXM3122	18TXM3214	18TXM3306
18TXM3031	18TXM3123	18TXM3215	18TXM3307
18TXM3032	18TXM3124	18TXM3216	18TXM3308
18TXM3033	18TXM3125	18TXM3217	18TXM3309
18TXM3034	18TXM3126	18TXM3218	18TXM3310
18TXM3035	18TXM3127	18TXM3219	18TXM3311
18TXM3036	18TXM3128	18TXM3220	18TXM3312
18TXM3037	18TXM3129	18TXM3221	18TXM3313
18TXM3038	18TXM3130	18TXM3222	18TXM3314
18TXM3039	18TXM3131	18TXM3223	18TXM3315
18TXM3040	18TXM3132	18TXM3224	18TXM3316
18TXM3041	18TXM3133	18TXM3225	18TXM3317
18TXM3042	18TXM3134	18TXM3226	18TXM3318
18TXM3043	18TXM3135	18TXM3227	18TXM3319
18TXM3044	18TXM3136	18TXM3228	18TXM3320
18TXM3045	18TXM3137	18TXM3229	18TXM3321
18TXM3046	18TXM3138	18TXM3230	18TXM3322
18TXM3047	18TXM3139	18TXM3231	18TXM3323
18TXM3048	18TXM3140	18TXM3232	18TXM3324
18TXM3049	18TXM3141	18TXM3233	18TXM3325
18TXM3050	18TXM3142	18TXM3234	18TXM3326
18TXM3051	18TXM3143	18TXM3235	18TXM3327
18TXM3052	18TXM3144	18TXM3236	18TXM3328
18TXM3053	18TXM3145	18TXM3237	18TXM3329
18TXM3054	18TXM3146	18TXM3238	18TXM3330
18TXM3055	18TXM3147	18TXM3239	18TXM3331
18TXM3056	18TXM3148	18TXM3240	18TXM3332
18TXM3106	18TXM3149	18TXM3241	18TXM3333
18TXM3107	18TXM3150	18TXM3242	18TXM3334
18TXM3108	18TXM3151	18TXM3243	18TXM3335
18TXM3109	18TXM3152	18TXM3244	18TXM3336
18TXM3110	18TXM3153	18TXM3245	18TXM3337
18TXM3111	18TXM3154	18TXM3246	18TXM3338

18TXM3339	18TXM3431	18TXM3523	18TXM3615
18TXM3340	18TXM3432	18TXM3524	18TXM3616
18TXM3341	18TXM3433	18TXM3525	18TXM3617
18TXM3342	18TXM3434	18TXM3526	18TXM3618
18TXM3343	18TXM3435	18TXM3527	18TXM3619
18TXM3344	18TXM3436	18TXM3528	18TXM3620
18TXM3345	18TXM3437	18TXM3529	18TXM3621
18TXM3346	18TXM3438	18TXM3530	18TXM3622
18TXM3347	18TXM3439	18TXM3531	18TXM3623
18TXM3348	18TXM3440	18TXM3532	18TXM3624
18TXM3349	18TXM3441	18TXM3533	18TXM3625
18TXM3350	18TXM3442	18TXM3534	18TXM3626
18TXM3351	18TXM3443	18TXM3535	18TXM3627
18TXM3352	18TXM3444	18TXM3536	18TXM3628
18TXM3353	18TXM3445	18TXM3537	18TXM3629
18TXM3354	18TXM3446	18TXM3538	18TXM3630
18TXM3355	18TXM3447	18TXM3539	18TXM3631
18TXM3356	18TXM3448	18TXM3540	18TXM3632
18TXM3406	18TXM3449	18TXM3541	18TXM3633
18TXM3407	18TXM3450	18TXM3542	18TXM3634
18TXM3408	18TXM3451	18TXM3543	18TXM3635
18TXM3409	18TXM3452	18TXM3544	18TXM3636
18TXM3410	18TXM3453	18TXM3545	18TXM3637
18TXM3411	18TXM3454	18TXM3546	18TXM3638
18TXM3412	18TXM3455	18TXM3547	18TXM3639
18TXM3413	18TXM3456	18TXM3548	18TXM3640
18TXM3414	18TXM3506	18TXM3549	18TXM3641
18TXM3415	18TXM3507	18TXM3550	18TXM3642
18TXM3416	18TXM3508	18TXM3551	18TXM3643
18TXM3417	18TXM3509	18TXM3552	18TXM3644
18TXM3418	18TXM3510	18TXM3553	18TXM3645
18TXM3419	18TXM3511	18TXM3554	18TXM3646
18TXM3420	18TXM3512	18TXM3555	18TXM3647
18TXM3421	18TXM3513	18TXM3556	18TXM3648
18TXM3422	18TXM3514	18TXM3606	18TXM3649
18TXM3423	18TXM3515	18TXM3607	18TXM3650
18TXM3424	18TXM3516	18TXM3608	18TXM3651
18TXM3425	18TXM3517	18TXM3609	18TXM3652
18TXM3426	18TXM3518	18TXM3610	18TXM3653
18TXM3427	18TXM3519	18TXM3611	18TXM3654
18TXM3428	18TXM3520	18TXM3612	18TXM3655
18TXM3429	18TXM3521	18TXM3613	18TXM3656
18TXM3430	18TXM3522	18TXM3614	18TXM3706

18TXM3707	18TXM3750	18TXM3842	18TXM3934
18TXM3708	18TXM3751	18TXM3843	18TXM3935
18TXM3709	18TXM3752	18TXM3844	18TXM3936
18TXM3710	18TXM3753	18TXM3845	18TXM3937
18TXM3711	18TXM3754	18TXM3846	18TXM3938
18TXM3712	18TXM3755	18TXM3847	18TXM3939
18TXM3713	18TXM3756	18TXM3848	18TXM3940
18TXM3714	18TXM3806	18TXM3849	18TXM3941
18TXM3715	18TXM3807	18TXM3850	18TXM3942
18TXM3716	18TXM3808	18TXM3851	18TXM3943
18TXM3717	18TXM3809	18TXM3852	18TXM3944
18TXM3718	18TXM3810	18TXM3853	18TXM3945
18TXM3719	18TXM3811	18TXM3854	18TXM3946
18TXM3720	18TXM3812	18TXM3855	18TXM3947
18TXM3721	18TXM3813	18TXM3856	18TXM3948
18TXM3722	18TXM3814	18TXM3906	18TXM3949
18TXM3723	18TXM3815	18TXM3907	18TXM3950
18TXM3724	18TXM3816	18TXM3908	18TXM3951
18TXM3725	18TXM3817	18TXM3909	18TXM3952
18TXM3726	18TXM3818	18TXM3910	18TXM3953
18TXM3727	18TXM3819	18TXM3911	18TXM3954
18TXM3728	18TXM3820	18TXM3912	18TXM3955
18TXM3729	18TXM3821	18TXM3913	18TXM3956
18TXM3730	18TXM3822	18TXM3914	18TXM4006
18TXM3731	18TXM3823	18TXM3915	18TXM4007
18TXM3732	18TXM3824	18TXM3916	18TXM4008
18TXM3733	18TXM3825	18TXM3917	18TXM4009
18TXM3734	18TXM3826	18TXM3918	18TXM4010
18TXM3735	18TXM3827	18TXM3919	18TXM4011
18TXM3736	18TXM3828	18TXM3920	18TXM4012
18TXM3737	18TXM3829	18TXM3921	18TXM4013
18TXM3738	18TXM3830	18TXM3922	18TXM4014
18TXM3739	18TXM3831	18TXM3923	18TXM4015
18TXM3740	18TXM3832	18TXM3924	18TXM4016
18TXM3741	18TXM3833	18TXM3925	18TXM4017
18TXM3742	18TXM3834	18TXM3926	18TXM4018
18TXM3743	18TXM3835	18TXM3927	18TXM4019
18TXM3744	18TXM3836	18TXM3928	18TXM4020
18TXM3745	18TXM3837	18TXM3929	18TXM4021
18TXM3746	18TXM3838	18TXM3930	18TXM4022
18TXM3747	18TXM3839	18TXM3931	18TXM4023
18TXM3748	18TXM3840	18TXM3932	18TXM4024
18TXM3749	18TXM3841	18TXM3933	18TXM4025

18TXM4026	18TXM4118	18TXM4210	18TXM4253
18TXM4027	18TXM4119	18TXM4211	18TXM4254
18TXM4028	18TXM4120	18TXM4212	18TXM4255
18TXM4029	18TXM4121	18TXM4213	18TXM4256
18TXM4030	18TXM4122	18TXM4214	18TXM4306
18TXM4031	18TXM4123	18TXM4215	18TXM4307
18TXM4032	18TXM4124	18TXM4216	18TXM4308
18TXM4033	18TXM4125	18TXM4217	18TXM4309
18TXM4034	18TXM4126	18TXM4218	18TXM4310
18TXM4035	18TXM4127	18TXM4219	18TXM4311
18TXM4036	18TXM4128	18TXM4220	18TXM4312
18TXM4037	18TXM4129	18TXM4221	18TXM4313
18TXM4038	18TXM4130	18TXM4222	18TXM4314
18TXM4039	18TXM4131	18TXM4223	18TXM4315
18TXM4040	18TXM4132	18TXM4224	18TXM4316
18TXM4041	18TXM4133	18TXM4225	18TXM4317
18TXM4042	18TXM4134	18TXM4226	18TXM4318
18TXM4043	18TXM4135	18TXM4227	18TXM4319
18TXM4044	18TXM4136	18TXM4228	18TXM4320
18TXM4045	18TXM4137	18TXM4229	18TXM4321
18TXM4046	18TXM4138	18TXM4230	18TXM4322
18TXM4047	18TXM4139	18TXM4231	18TXM4323
18TXM4048	18TXM4140	18TXM4232	18TXM4324
18TXM4049	18TXM4141	18TXM4233	18TXM4325
18TXM4050	18TXM4142	18TXM4234	18TXM4326
18TXM4051	18TXM4143	18TXM4235	18TXM4327
18TXM4052	18TXM4144	18TXM4236	18TXM4328
18TXM4053	18TXM4145	18TXM4237	18TXM4329
18TXM4054	18TXM4146	18TXM4238	18TXM4330
18TXM4055	18TXM4147	18TXM4239	18TXM4331
18TXM4056	18TXM4148	18TXM4240	18TXM4332
18TXM4106	18TXM4149	18TXM4241	18TXM4333
18TXM4107	18TXM4150	18TXM4242	18TXM4334
18TXM4108	18TXM4151	18TXM4243	18TXM4335
18TXM4109	18TXM4152	18TXM4244	18TXM4336
18TXM4110	18TXM4153	18TXM4245	18TXM4337
18TXM4111	18TXM4154	18TXM4246	18TXM4338
18TXM4112	18TXM4155	18TXM4247	18TXM4339
18TXM4113	18TXM4156	18TXM4248	18TXM4340
18TXM4114	18TXM4206	18TXM4249	18TXM4341
18TXM4115	18TXM4207	18TXM4250	18TXM4342
18TXM4116	18TXM4208	18TXM4251	18TXM4343
18TXM4117	18TXM4209	18TXM4252	18TXM4344

18TXM4345	18TXM4437	18TXM4529	18TXM4621
18TXM4346	18TXM4438	18TXM4530	18TXM4622
18TXM4347	18TXM4439	18TXM4531	18TXM4623
18TXM4348	18TXM4440	18TXM4532	18TXM4624
18TXM4349	18TXM4441	18TXM4533	18TXM4625
18TXM4350	18TXM4442	18TXM4534	18TXM4626
18TXM4351	18TXM4443	18TXM4535	18TXM4627
18TXM4352	18TXM4444	18TXM4536	18TXM4628
18TXM4353	18TXM4445	18TXM4537	18TXM4629
18TXM4354	18TXM4446	18TXM4538	18TXM4630
18TXM4355	18TXM4447	18TXM4539	18TXM4631
18TXM4356	18TXM4448	18TXM4540	18TXM4632
18TXM4406	18TXM4449	18TXM4541	18TXM4633
18TXM4407	18TXM4450	18TXM4542	18TXM4634
18TXM4408	18TXM4451	18TXM4543	18TXM4635
18TXM4409	18TXM4452	18TXM4544	18TXM4636
18TXM4410	18TXM4453	18TXM4545	18TXM4637
18TXM4411	18TXM4454	18TXM4546	18TXM4638
18TXM4412	18TXM4455	18TXM4547	18TXM4639
18TXM4413	18TXM4456	18TXM4548	18TXM4640
18TXM4414	18TXM4506	18TXM4549	18TXM4641
18TXM4415	18TXM4507	18TXM4550	18TXM4642
18TXM4416	18TXM4508	18TXM4551	18TXM4643
18TXM4417	18TXM4509	18TXM4552	18TXM4644
18TXM4418	18TXM4510	18TXM4553	18TXM4645
18TXM4419	18TXM4511	18TXM4554	18TXM4646
18TXM4420	18TXM4512	18TXM4555	18TXM4647
18TXM4421	18TXM4513	18TXM4556	18TXM4648
18TXM4422	18TXM4514	18TXM4606	18TXM4649
18TXM4423	18TXM4515	18TXM4607	18TXM4650
18TXM4424	18TXM4516	18TXM4608	18TXM4651
18TXM4425	18TXM4517	18TXM4609	18TXM4652
18TXM4426	18TXM4518	18TXM4610	18TXM4653
18TXM4427	18TXM4519	18TXM4611	18TXM4654
18TXM4428	18TXM4520	18TXM4612	18TXM4655
18TXM4429	18TXM4521	18TXM4613	18TXM4656
18TXM4430	18TXM4522	18TXM4614	18TXM4706
18TXM4431	18TXM4523	18TXM4615	18TXM4707
18TXM4432	18TXM4524	18TXM4616	18TXM4708
18TXM4433	18TXM4525	18TXM4617	18TXM4709
18TXM4434	18TXM4526	18TXM4618	18TXM4710
18TXM4435	18TXM4527	18TXM4619	18TXM4711
18TXM4436	18TXM4528	18TXM4620	18TXM4712

18TXM4713	18TXM4756	18TXM4848	18TXM4940
18TXM4714	18TXM4806	18TXM4849	18TXM4941
18TXM4715	18TXM4807	18TXM4850	18TXM4942
18TXM4716	18TXM4808	18TXM4851	18TXM4943
18TXM4717	18TXM4809	18TXM4852	18TXM4944
18TXM4718	18TXM4810	18TXM4853	18TXM4945
18TXM4719	18TXM4811	18TXM4854	18TXM4946
18TXM4720	18TXM4812	18TXM4855	18TXM4947
18TXM4721	18TXM4813	18TXM4856	18TXM4948
18TXM4722	18TXM4814	18TXM4906	18TXM4949
18TXM4723	18TXM4815	18TXM4907	18TXM4950
18TXM4724	18TXM4816	18TXM4908	18TXM4951
18TXM4725	18TXM4817	18TXM4909	18TXM4952
18TXM4726	18TXM4818	18TXM4910	18TXM4953
18TXM4727	18TXM4819	18TXM4911	18TXM4954
18TXM4728	18TXM4820	18TXM4912	18TXM4955
18TXM4729	18TXM4821	18TXM4913	18TXM4956
18TXM4730	18TXM4822	18TXM4914	18TXM5006
18TXM4731	18TXM4823	18TXM4915	18TXM5007
18TXM4732	18TXM4824	18TXM4916	18TXM5008
18TXM4733	18TXM4825	18TXM4917	18TXM5009
18TXM4734	18TXM4826	18TXM4918	18TXM5010
18TXM4735	18TXM4827	18TXM4919	18TXM5011
18TXM4736	18TXM4828	18TXM4920	18TXM5012
18TXM4737	18TXM4829	18TXM4921	18TXM5013
18TXM4738	18TXM4830	18TXM4922	18TXM5014
18TXM4739	18TXM4831	18TXM4923	18TXM5015
18TXM4740	18TXM4832	18TXM4924	18TXM5016
18TXM4741	18TXM4833	18TXM4925	18TXM5017
18TXM4742	18TXM4834	18TXM4926	18TXM5018
18TXM4743	18TXM4835	18TXM4927	18TXM5019
18TXM4744	18TXM4836	18TXM4928	18TXM5020
18TXM4745	18TXM4837	18TXM4929	18TXM5021
18TXM4746	18TXM4838	18TXM4930	18TXM5022
18TXM4747	18TXM4839	18TXM4931	18TXM5023
18TXM4748	18TXM4840	18TXM4932	18TXM5024
18TXM4749	18TXM4841	18TXM4933	18TXM5025
18TXM4750	18TXM4842	18TXM4934	18TXM5026
18TXM4751	18TXM4843	18TXM4935	18TXM5027
18TXM4752	18TXM4844	18TXM4936	18TXM5028
18TXM4753	18TXM4845	18TXM4937	18TXM5029
18TXM4754	18TXM4846	18TXM4938	18TXM5030
18TXM4755	18TXM4847	18TXM4939	18TXM5031

18TXM5032	18TXM5126	18TXM5224	18TXM5328
18TXM5033	18TXM5127	18TXM5225	18TXM5329
18TXM5034	18TXM5128	18TXM5226	18TXM5330
18TXM5035	18TXM5129	18TXM5227	18TXM5331
18TXM5036	18TXM5130	18TXM5228	18TXM5332
18TXM5037	18TXM5131	18TXM5229	18TXM5333
18TXM5038	18TXM5132	18TXM5230	18TXM5334
18TXM5039	18TXM5133	18TXM5231	18TXM5335
18TXM5040	18TXM5134	18TXM5232	18TXM5336
18TXM5041	18TXM5135	18TXM5233	18TXM5337
18TXM5042	18TXM5136	18TXM5234	18TXM5338
18TXM5043	18TXM5137	18TXM5235	18TXM5339
18TXM5044	18TXM5138	18TXM5236	18TXM5340
18TXM5045	18TXM5139	18TXM5237	18TXM5341
18TXM5048	18TXM5140	18TXM5238	18TXM5342
18TXM5049	18TXM5141	18TXM5239	18TXM5343
18TXM5050	18TXM5142	18TXM5240	18TXM5344
18TXM5051	18TXM5143	18TXM5241	18TXM5414
18TXM5052	18TXM5144	18TXM5242	18TXM5415
18TXM5053	18TXM5145	18TXM5243	18TXM5416
18TXM5054	18TXM5149	18TXM5244	18TXM5417
18TXM5055	18TXM5150	18TXM5306	18TXM5418
18TXM5056	18TXM5151	18TXM5307	18TXM5419
18TXM5106	18TXM5154	18TXM5308	18TXM5420
18TXM5107	18TXM5155	18TXM5309	18TXM5421
18TXM5108	18TXM5206	18TXM5310	18TXM5422
18TXM5109	18TXM5207	18TXM5311	18TXM5423
18TXM5110	18TXM5208	18TXM5312	18TXM5424
18TXM5111	18TXM5209	18TXM5313	18TXM5425
18TXM5112	18TXM5210	18TXM5314	18TXM5426
18TXM5113	18TXM5211	18TXM5315	18TXM5427
18TXM5114	18TXM5212	18TXM5316	18TXM5428
18TXM5115	18TXM5213	18TXM5317	18TXM5429
18TXM5116	18TXM5214	18TXM5318	18TXM5430
18TXM5117	18TXM5215	18TXM5319	18TXM5431
18TXM5118	18TXM5216	18TXM5320	18TXM5432
18TXM5119	18TXM5217	18TXM5321	18TXM5433
18TXM5120	18TXM5218	18TXM5322	18TXM5434
18TXM5121	18TXM5219	18TXM5323	18TXM5435
18TXM5122	18TXM5220	18TXM5324	18TXM5436
18TXM5123	18TXM5221	18TXM5325	18TXM5437
18TXM5124	18TXM5222	18TXM5326	18TXM5438
18TXM5125	18TXM5223	18TXM5327	18TXM5439

18TXM5440	18TXM5627	18TXM5823	18TXM6030
18TXM5441	18TXM5628	18TXM5824	18TXM6031
18TXM5514	18TXM5629	18TXM5825	18TXM6032
18TXM5515	18TXM5630	18TXM5826	18TXM6116
18TXM5516	18TXM5631	18TXM5827	18TXM6117
18TXM5517	18TXM5632	18TXM5828	18TXM6118
18TXM5518	18TXM5633	18TXM5829	18TXM6119
18TXM5519	18TXM5634	18TXM5830	18TXM6120
18TXM5520	18TXM5635	18TXM5831	18TXM6121
18TXM5521	18TXM5636	18TXM5832	18TXM6122
18TXM5522	18TXM5637	18TXM5833	18TXM6123
18TXM5523	18TXM5638	18TXM5916	18TXM6124
18TXM5524	18TXM5639	18TXM5917	18TXM6125
18TXM5525	18TXM5640	18TXM5918	18TXM6126
18TXM5526	18TXM5714	18TXM5919	18TXM6127
18TXM5527	18TXM5715	18TXM5920	18TXM6128
18TXM5528	18TXM5716	18TXM5921	18TXM6129
18TXM5529	18TXM5717	18TXM5922	18TXM6130
18TXM5530	18TXM5718	18TXM5923	18TXM6131
18TXM5531	18TXM5719	18TXM5924	18TXM6216
18TXM5532	18TXM5720	18TXM5925	18TXM6217
18TXM5533	18TXM5721	18TXM5926	18TXM6218
18TXM5534	18TXM5722	18TXM5927	18TXM6219
18TXM5535	18TXM5723	18TXM5928	18TXM6220
18TXM5536	18TXM5724	18TXM5929	18TXM6221
18TXM5537	18TXM5725	18TXM5930	18TXM6222
18TXM5538	18TXM5726	18TXM5931	18TXM6223
18TXM5539	18TXM5727	18TXM5932	18TXM6224
18TXM5540	18TXM5728	18TXM5933	18TXM6225
18TXM5541	18TXM5729	18TXM6016	18TXM6226
18TXM5614	18TXM5730	18TXM6017	18TXM6227
18TXM5615	18TXM5731	18TXM6018	18TXM6228
18TXM5616	18TXM5732	18TXM6019	18TXM6229
18TXM5617	18TXM5733	18TXM6020	18TXM6230
18TXM5618	18TXM5735	18TXM6021	18TXM6316
18TXM5619	18TXM5736	18TXM6022	18TXM6317
18TXM5620	18TXM5816	18TXM6023	18TXM6318
18TXM5621	18TXM5817	18TXM6024	18TXM6319
18TXM5622	18TXM5818	18TXM6025	18TXM6320
18TXM5623	18TXM5819	18TXM6026	18TXM6321
18TXM5624	18TXM5820	18TXM6027	18TXM6322
18TXM5625	18TXM5821	18TXM6028	18TXM6323
18TXM5626	18TXM5822	18TXM6029	18TXM6324

18TXM6325
18TXM6326
18TXM6327
18TXM6328
18TXM6329
18TXM6330
18TXM6419
18TXM6420
18TXM6421
18TXM6422
18TXM6423
18TXM6424
18TXM6425
18TXM6426
18TXM6427
18TXM6428
18TXM6429
18TXM6519
18TXM6520
18TXM6521
18TXM6522
18TXM6523
18TXM6524
18TXM6525
18TXM6526
18TXM6527
18TXM6619
18TXM6620
18TXM6621
18TXM6622

2 LiDAR Acquisition Report

2.1 PROJECT DESCRIPTION

The project area for Connecticut Phase II included approximately 657 contiguous square miles including a buffer of 200 meters. LiDAR sensor data were collected with an Optech ALTM3100EA LIDAR System. No imagery was requested or delivered. The data was delivered in the UTM coordinate system, meters, zone 18, horizontal datum NAD83, and vertical datum NGVD88, Geoid 09. Deliverables for the project included a raw (unclassified) calibrated LiDAR point cloud, survey control, and a final control report.

2.2 MISSION PLANNING

GPS Base Stations

Flight planning constrained all GPS baselines to a maximum of 25 miles. One GPS base station was required as shown.




Figure 2: GPS Stations

LiDAR Flight Plan

LiDAR was flown based on the following sensor parameters and flight plan to achieve maximum efficiency and nominal pulse densities.

SENSOR PARAMETERS Optech ALTM3100EA LIDAR System Sensor Parameters	
Pulse Rate	70,000
Field of View	21.5 degrees
Side Lap	50%
Average Density	0.7 ppm

Table 1: Sensor Parameters




Figure 3: Flight Layout

CONTROL LAYOUT

A total of 7 distributed control points were planned and collected with static GPS observations as shown.




Figure 4: Control Points

2.3 ACQUISITION

Airborne LiDAR

Data acquisition commenced on December 13, 2011(Julian day 347) and was completed on December 19, 2011(Julian day 353). 11 missions were flown to complete the acquisition. Flight lines were flown according to the proposed flight layout with no changes. There were no unusual occurrences and the acquisition went according to plan. The aircraft based out of Waterbury-Oxford (KOXC) airport. NGS monument G59 was used as the primary base station for airborne missions with an offset point set nearby as a backup GPS base station.

Survey Control

Compliance with the accuracy standard was ensured through the collection of GPS ground control during the acquisition of aerial LiDAR and the establishment of a GPS base station operating at the airport. In

addition to the base stations, CORS bases may have been used to supplement the solutions. The following criteria were adhered to during control point collection.

1. Each point was collected during periods of very low (<2) DOP.
2. No point was collected with a base line greater than 25 miles.
3. Each point was collected at a place of constant slope so as to minimize any errors introduced through LiDAR triangulation.
4. Each point was collected at moderate intensity surfaces so any intensity based anomalies could be avoided.

Number	Easting	Northing	Known Z
St3	665137.8	4626931	308.467
St4	653224.1	4631545	233.935
St6	642245.9	4652638	240.561
St7	630707.3	4649207	212.347
Stc1	651158.8	4614882	313.686
Stc2	626508.7	4610795	78.36
Stc5	626037.2	4637741	191.415

Table 3: Control points and accuracy assessment

2.4 PROCESSING

LiDAR Calibration

The calibration process considered all errors inherent with the equipment including errors in GPS, IMU, and sensor specific parameters. Adjustments were made to achieve a flight line to flight line data match (relative calibration) and subsequently adjusted to control for absolute accuracy. Process steps to achieve this are as follows:

1. Rigorous LiDAR calibration: all sources of error such as the sensor's ranging and torsion parameters, atmospheric variables, GPS conditions, and IMU offsets were analyzed and removed to the highest level possible. This method addresses all errors, both vertical and horizontal in nature. Ranging, atmospheric variables, and GPS conditions affect the vertical position of the surface, whereas IMU offsets and torsion parameters affect the data horizontally. The horizontal accuracy is proven through repeatability: when the position of features remains constant no matter what direction the plane was flying and no matter where the feature is positioned within the swath, relative horizontal accuracy is achieved.
2. Absolute horizontal accuracy is achieved through the use of differential GPS with base lines shorter than 25 miles. The base station is set at a temporary monument that is 'tied-in' to the CORS network. The same position is used for every lift, ensuring that any errors in its position will affect all data equally and can therefore be removed equally.
3. Vertical accuracy is achieved through the adjustment to ground control survey points within the finished product. Although the base station has absolute vertical accuracy, adjustments to sensor parameters introduces vertical error that must be normalized in the final (mean) adjustment. The minimum expected horizontal accuracy was tested during the boresight process to meet or exceed the National Standard for Spatial Data Accuracy (NSSDA) for a Horizontal accuracy of 1 meter RMSE or better and a Vertical Accuracy of $RMSE(z) \leq 9.25$ cm

2.5 QA/QC

Once all lifts are horizontally and vertically calibrated a final vertical accuracy check against the control is performed. The result is analyzed against the project specified accuracy to make sure it meets the

requirement. The final accuracy for this project yielded a **0.024 meter RMSEz @ 95% confidence level**. Following are list of all control points compared to the final calibrated LiDAR surface.

Number	Easting	Northing	Known Z	LiDAR Z	Delta Z
St3	665137.8	4626931	308.467	308.47	0.003
St4	653224.1	4631545	233.935	233.94	0.005
St6	642245.9	4652638	240.561	240.56	-0.001
St7	630707.3	4649207	212.347	212.35	0.003
Stc1	651158.8	4614882	313.686	313.72	0.034
Stc2	626508.7	4610795	78.36	78.41	0.05
Stc5	626037.2	4637741	191.415	191.4	-0.015

Table 4: Final accuracy

2.6 Final Deliverables

Final project deliverables:

1. Calibrated raw (unclassified) LiDAR point clouds by flight line in las format
2. Survey Control points in excel format
3. Survey control accuracy report in excel format
4. Final Report PDF

Projections/Datums

UTM coordinate system, meters, zone 18, horizontal datum NAD83, vertical datum NGVD88, Geoid 09

3 LiDAR Processing & Qualitative Assessment

3.1 Data Classification and Editing

Laser Mapping Specialist delivered LiDAR swaths to Dewberry that were calibrated and projected to project specifications. Dewberry processed the data using GeoCue and TerraScan software. The initial step is the setup of the GeoCue project, which is done by importing a project defined tile boundary index encompassing the entire project area. The acquired 3D laser point clouds, in LAS binary format, were imported into the GeoCue project and tiled according to the project tile grid. Once tiled, the laser points were classified using a proprietary routine in TerraScan. This routine removes any obvious outliers from the dataset following which the ground layer is extracted from the point cloud. The ground extraction process encompassed in this routine takes place by building an iterative surface model.

This surface model is generated using three main parameters: building size, iteration angle and iteration distance. The initial model is based on low points being selected by a "roaming window" with the assumption is that these are the ground points. The size of this roaming window is determined by the building size parameter. The low points are triangulated and the remaining points are evaluated and subsequently added to the model if they meet the iteration angle and distance constraints. This process is repeated until no additional points are added within iterations. A second critical parameter is the maximum terrain angle constraint, which determines the maximum terrain angle allowed within the classification model.

Once the initial ground routine has been performed on the data, Dewberry creates Delta Z (DZ) orthos to check the relative accuracy of the LiDAR data. These orthos compare the elevations of LiDAR points from overlapping flight lines on a 1 meter pixel cell size basis. If the elevations of points within each pixel are within 10 cm of each other, the pixel is colored green. If the elevations of points within each pixel are between 10 cm and 20 cm of each other, the pixel is colored yellow, and if the elevations of points within each pixel are greater than 20 cm in difference, the pixel is colored red. Pixels that do not contain points from overlapping flight lines are colored according to their intensity values. DZ orthos can be created using the full point cloud or ground only points and are used to review and verify the calibration of the data is acceptable. Some areas are expected to show sections or portions of red, including terrain variations, slope changes, and vegetated areas or buildings if the full point cloud is used. However, large or continuous sections of yellow or red pixels can indicate the data was not calibrated correctly or that there were issues during acquisition that could affect the usability of the data. The DZ orthos for Connecticut showed that the data was calibrated correctly with no issues that would affect its usability. The figure below shows an example of the DZ orthos.



Figure 3: DZ orthos created from ground only points. Some red pixels are visible along embankments and sloped terrain, as expected. Open, flat areas are green indicating the calibration and relative accuracy of the data is acceptable.

Dewberry utilizes a variety of software suites for data processing. After the initial ground classification, each tile was imported into Terrascan and a surface model was created to examine the ground classification. Dewberry analysts visually reviewed the ground surface model and corrected errors in the ground classification such as vegetation, buildings, and bridges that were present following the initial processing. Dewberry analysts employ 3D visualization techniques to view the point cloud at multiple angles and in profile to ensure that non-ground points are removed from the ground classification. After the ground classification corrections were completed, the dataset was processed through a water classification routine that utilizes breaklines compiled by Dewberry to automatically classify hydro features. The water classification routine selects ground points within the breakline polygons and re-classifies them as class 9, water.

Terrascan was also used to create model key points. An algorithm is defined that intelligently thins bare earth ground points so that points necessary to define breaks and elevation changes in the terrain are kept while unnecessary or redundant points are not included in the model key points. The model key points are then written to its own file, according to the project tile grid, with all points located in class 8.

GeoCue was used to create the bare earth only LiDAR tiles, first return only LiDAR tiles, and last return only LiDAR tiles. For bare earth only LiDAR tiles, class 2 points are filtered from the full point cloud data and written to its own file, according to the project tile grid.

For first return and last return tiles, the desired echo return is filtered from the full point cloud and written to its own file, according to the project tile grid. The first return and last return files include the desired return from all classes. The points for these files are located in class 1.

After all processing and classification has been completed, GeoCue software is used to update the LAS version, projection information, creation day, and creation year of every LiDAR file.

3.2 *Qualitative Assessment*

Dewberry qualitative assessment utilizes a combination of statistical analysis and interpretative methodology to assess the quality of the data for a bare-earth digital elevation model (DEM). This process looks for anomalies in the data and also identifies areas where man-made structures or vegetation points may not have been classified properly to produce a bare-earth model.

Within this review of the LiDAR data, two fundamental questions were addressed:

- Did the LiDAR system perform to specifications?
- Did the vegetation removal process yield desirable results for the intended bare-earth terrain product?

Mapping standards today address the quality of data by quantitative methods. If the data are tested and found to be within the desired accuracy standard, then the data set is typically accepted. Now with the proliferation of LiDAR, new issues arise due to the vast amount of data. Unlike photogrammetrically-derived DEMs where point spacing can be eight meters or more, LiDAR nominal point spacing for this project is 1 point per 0.7 square meters. The end result is that millions of elevation points are measured to a level of accuracy previously unseen for traditional elevation mapping technologies and vegetated areas are measured that would be nearly impossible to survey by other means. The downside is that with millions of points, the dataset is statistically bound to have some errors both in the measurement process and in the artifact removal process.

As previously stated, the quantitative analysis addresses the quality of the data based on absolute accuracy. This accuracy is directly tied to the comparison of the discrete measurement of the survey checkpoints and that of the interpolated value within the three closest LiDAR points that constitute the vertices of a three-dimensional triangular face of the TIN. Therefore, the end result is that only a small sample of the LiDAR data is actually tested. However there is an increased level of confidence with LiDAR data due to the relative accuracy. This relative accuracy is based on how well one LiDAR point "fits" in comparison to the next contiguous LiDAR measurement, and is verified with DZ orthos. Once the absolute and relative accuracy has been ascertained, the next stage is to address the cleanliness of the data for a bare-earth DEM.

By using survey checkpoints to compare the data, the absolute accuracy is verified, but this also allows us to understand if the artifact removal process was performed correctly. To reiterate the quantitative approach, if the LiDAR sensor operated correctly over open terrain areas, then it most likely operated correctly over the vegetated areas. This does not mean that the entire bare-earth was measured; only that the elevations surveyed are most likely accurate (including elevations of treetops, rooftops, etc.). In the event that the LiDAR pulse filtered through the vegetation and was able to measure the true surface (as well as measurements on the surrounding vegetation) then the level of accuracy of the vegetation removal process can be tested as a by-product.

To fully address the data for overall accuracy and quality, the level of cleanliness (or removal of above-ground artifacts) is paramount. Since there are currently no effective automated testing procedures to measure cleanliness, Dewberry employs a combination of statistical and visualization processes. This includes creating pseudo image products such as LiDAR orthos produced from the intensity returns, Triangulated Irregular Network (TIN)'s, Digital Elevation Models (DEM) and 3-dimensional models. By creating multiple images and using overlay techniques, not only can potential errors be found, but Dewberry can also find where the data meets and exceeds expectations. This report will present representative examples where the LiDAR and post processing had issues as well as examples of where the LiDAR performed well.

Dewberry utilizes GeoCue software as the primary geospatial process management system. GeoCue is a three tier, multi-user architecture that uses .NET technology from Microsoft. .NET technology provides the real-time notification system that updates users with real-time project status, regardless of who makes changes to project entities. GeoCue uses database technology for sorting project metadata. Dewberry uses Microsoft SQL Server as the database of choice. Specific analysis is conducted in Terrascan and QT Modeler environments.

Following the completion of LiDAR point classification, the Dewberry qualitative assessment process flow for the Connecticut LiDAR project incorporated the following reviews:

1. *Format:* The LAS files are verified to meet project specifications. The LAS files conform to the specifications outlined below.
 - Format, Echos, Intensity
 - o LAS format 1.2, point data record format 1
 - o Point data record format 1
 - o Multiple returns (echos) per pulse
 - o Intensity values populated for each point
 - ASPRS classification scheme
 - o Class 1 – unclassified
 - o Class 2 – ground
 - o Class 7 – Noise
 - o Class 9 – Water
 - Projection
 - o Datum – North American Datum 1983
 - o Projected Coordinate System –UTM Zone 18N
 - o Units – Meters
 - o Vertical Datum – North American Vertical Datum 1988, Geoid 09
 - o Vertical Units - Meters

- LAS header information:
 - Class (Integer)
 - GPS Week Time (0.0001 seconds)
 - Easting (0.01 foot)
 - Northing (0.01 foot)
 - Elevation (0.01 foot)
 - Echo Number (Integer 1 to 4)
 - Echo (Integer 1 to 4)
 - Intensity (8 bit integer)
 - Flight Line (Integer)
 - Scan Angle (Integer degree)

- 2. *Data density, data voids:* The LAS files are used to produce Digital Elevation Models using the commercial software package “QT Modeler” which creates a 3-dimensional data model derived from Class 2 (ground points) in the LAS files. Grid spacing is based on the project density deliverable requirement for un-obscured areas. For the Connecticut LiDAR project it is stipulated that the minimum post spacing in un-obscured areas should be 1 point per 0.7 square meter.
 - a. The Connecticut LiDAR data has full coverage. Only acceptable voids (areas with no LiDAR returns in the LAS files) are present in the LiDAR, including voids caused by bodies of water.

- 3. *Bare earth quality:* Dewberry reviewed the cleanliness of the bare earth to ensure the ground has correct definition, meets the project requirements, there is correct classification of points, and there are less than 5% residual artifacts.
 - a. *Building Removal:* Large buildings, unique construction, and buildings built on sloped terrain or built into the ground can make a noticeable impact on the bare earth DEM once they have been removed, often in the form of large void areas with obvious triangulation or interpolation across the area and general lack of detail in the ground where the structure stood. Dewberry analysts verified that structures have been removed from the ground, that areas along slopes missing definition are due to structural or vegetation removal and not aggressive classification, and that holes or removal of ground is accurate.
 - b. *Flight Line Ridges:* Dewberry reviewed DZ orthos to ensure acceptable calibration and relative accuracy of the Connecticut data. No major issues were identified.

3.3 Conclusion

The dataset conforms to project specifications for format and header values. The spatial projection information and classification of points is correct. Buildings, vegetation and other artifacts have been removed from the bare earth ground.

4 Survey Vertical Accuracy Checkpoints

POINT ID	NORTHING (M)	EASTING (M)	ELEVS. (M)
FOREST SHOTS (FO)			
FO-1	4655919.902	630932.384	215.753
FO-2	4650999.752	636642.255	204.528
FO-3	4654432.797	646733.613	424.109
FO-4	4640903.731	626630.644	164.511
FO-5	4645158.141	641506.330	204.542
FO-7	4640643.657	651198.872	277.775
FO-8	4631289.118	630047.361	360.779
FO-9	4632593.658	643110.699	356.466
FO-10	4632501.124	657795.383	285.859
FO-11	4627541.073	627558.913	411.561
FO-12	4624455.317	636888.234	385.627
FO-13	4625328.760	649251.842	368.172
FO-14	4626567.477	663717.338	273.975
FO-15	4619840.814	630991.391	361.663
FO-16	4616705.365	645477.997	282.117
FO-17	4617469.718	661494.037	168.313
FO-18	4610736.382	626523.777	78.319
FO-19	4609926.826	633601.273	111.201
FO-20	4609934.383	641989.869	288.784
GRASS, WEEDS, CROPS (GWC)			
GWC-1	4653160.921	631805.184	235.530
GWC-2	4656011.696	642963.220	254.653
GWC-3	4645849.592	626637.820	248.879
GWC-4	4644956.588	633612.288	195.814
GWC-5	4648293.844	643116.053	462.023
GWC-6	4645104.231	648515.023	430.551
GWC-7	4635895.546	632368.874	409.276
GWC-8	4636319.598	645382.541	392.900
GWC-9	4630001.320	653703.182	300.566
GWC-10	4632549.183	638539.528	202.669
GWC-11	4625017.312	630139.695	122.717
GWC-12	4622110.406	635957.866	388.018
GWC-13	4622822.283	645955.391	302.555

GWC-14	4621573.418	660192.692	249.020
GWC-15	4616062.743	631325.724	323.330
GWC-16	4613437.650	646066.527	258.232
GWC-17	4618785.601	655615.333	321.641
GWC-18	4610379.923	631041.693	149.142
GWC-19	4606783.943	637504.060	129.260
GWC-20	4612383.644	650236.517	311.583
GWC-21	4628395.832	663650.101	324.670
OPEN TERRAIN (OT)			
OT-1	4648794.700	630921.056	205.071
OT-2	4654374.130	638262.959	202.631
OT-3	4652226.339	643858.686	236.062
OT-4	4649978.635	648489.491	366.311
OT-5	4637784.650	626018.958	187.732
OT-6	4643591.841	635685.893	165.114
OT-7	4639750.449	642445.610	280.981
OT-8	4635251.585	652943.372	225.550
OT-9	4631040.040	635086.226	134.015
OT-11	4620663.777	627038.921	120.068
OT-12	4618112.075	637544.847	219.130
OT-13	4625539.396	643145.813	299.451
OT-14	4625428.435	656541.928	155.778
OT-15	4615253.610	627301.507	124.102
OT-16	4621300.385	650862.527	276.224
OT-17	4623056.440	664780.636	260.455
OT-18	4607501.147	628540.949	96.745
OT-19	4612796.513	640026.268	155.182
OT-20	4609031.203	646179.498	275.161
OT-21	4615205.252	653027.816	256.685

Table 5: Connecticut LiDAR surveyed accuracy checkpoints

4.1 Survey Checkpoints not used in vertical accuracy testing.

Two (2) checkpoints were surveyed in non-ideal locations for LiDAR accuracy testing. One forest terrain checkpoint was not used because it was located near impenetrable brush that did not give the LiDAR sensor an adequate chance to measure the ground surface. Additionally, one open terrain checkpoint was not used because it was located near vegetation.

Additional checkpoints are normally surveyed in case some of the checkpoints are deemed unusable. Even after removing these two checkpoints from the dataset, there were still 60

checkpoints remaining for the vertical accuracy testing, meeting project requirements of 60 total checkpoints. Table 6, below, identifies checkpoints not used in the vertical accuracy testing.

Point ID	Easting	Northing	Elevation
OT-10	647785.96	4630481.65	391.19
FO-6	634224.57	4638883.00	371.23

Table 6: Checkpoints not used in vertical accuracy testing.

Below are examples of the two checkpoints that were not used in vertical accuracy testing.



Figure 4: Survey Checkpoint OT-10. This checkpoint is located near downed vegetation which may have been different at time of the LiDAR collection.



Figure 5: Survey Checkpoint FO-6. This checkpoint was located near impenetrable brush that did not give the LiDAR sensor an adequate chance to measure the ground surface

5 LiDAR Vertical Accuracy Statistics & Analysis

5.1 Background

Dewberry tests and reviews project data both quantitatively (for accuracy) and qualitatively (for usability).

For quantitative assessment (i.e. vertical accuracy assessment), sixty-two (62) check points were surveyed for the project and are located within open terrain, grass, weeds, crops, and forest land cover categories. The checkpoints were surveyed for the project using RTK survey methods. A survey report was produced which details and validates how the survey was completed for this project.

Checkpoints were evenly distributed throughout the project area so as to cover as many flight lines as possible using the “dispersed method” of placement. Only sixty (60) check points were used to calculate the vertical accuracy as two (2) checkpoints were collected in inappropriate locations.

5.2 Vertical Accuracy Test Procedures

FVA (Fundamental Vertical Accuracy) is determined with check points located only in land cover category (1), open terrain (grass, dirt, sand, and/or rocks), where there is a very high probability that the LiDAR sensor will have detected the bare-earth ground surface and where random errors are expected to

follow a normal error distribution. The FVA determines how well the calibrated LiDAR sensor performed. With a normal error distribution, the vertical accuracy at the 95% confidence level is computed as the vertical root mean square error (RMSEz) of the checkpoints x 1.9600. For the Connecticut LiDAR project, vertical accuracy must be 18.5 cm or less based on an RMSEz of 9.25 cm x 1.9600.

CVA (Consolidated Vertical Accuracy) is determined with all checkpoints in all land cover categories combined where there is a possibility that the LiDAR sensor and post-processing may yield elevation errors that do not follow a normal error distribution. CVA at the 95% confidence level equals the 95th percentile error for all checkpoints in all land cover categories combined. The target CVA has not been defined for this dataset.

The relevant testing criteria are summarized in Table 7.

Quantitative Criteria	Measure of Acceptability
Fundamental Vertical Accuracy (FVA) in open terrain using RMSEz *1.9600	18.5 cm (based on RMSEz * 1.9600)

Table 7: Acceptance Criteria

5.3 Vertical Accuracy Testing Steps

The primary QA/QC vertical accuracy testing steps used by Dewberry are summarized as follows:

1. Dewberry's team surveyed QA/QC vertical checkpoints in accordance with the project's specifications. Figure 6 shows the location of the checkpoints.
2. Next, Dewberry interpolated the bare-earth LiDAR DEM to provide the z-value for each of the 60 checkpoints.
3. Dewberry then computed the associated z-value differences between the interpolated z-value from the LiDAR data and the ground truth survey checkpoints and computed CVA values.
4. The data were analyzed by Dewberry to assess the accuracy of the data. The review process examined the various accuracy parameters as defined by the scope of work. The overall descriptive statistics of each dataset were computed to assess any trends or anomalies. This report provides tables, graphs and figures to summarize and illustrate data quality.

Figure 6 shows the location of the QA/QC checkpoints within the project area.




Figure 6: Location of QA/QC Checkpoints

5.4 Vertical Accuracy Results

Table 8 summarizes the tested vertical accuracy resulting from a comparison of the surveyed checkpoints to the elevation values present within the LiDAR LAS files.

Land Cover Category	# of Points	FVA — Fundamental Vertical Accuracy (RMSE _z x 1.9600) Spec=0.185 m	CVA — Consolidated Vertical Accuracy (95th Percentile)	SVA-Supplemental Vertical Accuracy (95 th Percentile)
Consolidated	60		0.300	
Open Terrain	20	0.179		0.176
Grass/Weeds/Crops	21			0.333
Forest	19			0.279

Table 8: FVA and CVA Vertical Accuracy at 95% Confidence Level

The RMSE_z for open terrain checkpoints tested 0.091 m, within the target criteria of 0.0925 m. Compared with the 0.185 m specification, the FVA tested 0.179 m at the 95% confidence level based on RMSE_z x 1.9600.

Table 10 provides overall descriptive statistics.

100 % of Totals	RMSE (m) Open Terrain Spec=0.0925 m	Mean (m)	Median (m)	Skew	Std Dev (m)	# of Points	Min (m)	Max (m)
Consolidated	0.149	0.09	0.06	0.40	0.12	60	-0.16	0.35
Open Terrain	0.091	0.04	0.03	0.58	0.09	20	-0.11	0.23
Grass/Weeds/Crops	0.194	0.13	0.13	-0.18	0.15	21	-0.16	0.35
Forest	0.140	0.10	0.07	0.52	0.10	19	-0.06	0.30

Table 10: Overall Descriptive Statistics

5.5 Conclusion

Based on the vertical accuracy testing conducted by Dewberry, the LiDAR dataset for the Connecticut LiDAR Project satisfies the project's pre-defined vertical accuracy criteria.

6 Breakline Production & Qualitative Assessment Report


6.1 Breakline Production Methodology

Dewberry used GeoCue software to develop LiDAR stereo models of the Connecticut LiDAR Project area so the LiDAR derived data could be viewed in 3-D stereo using Socet Set softcopy photogrammetric software. Using LiDARgrammetry procedures with LiDAR intensity imagery, Dewberry stereo-compiled the two types of hard breaklines in accordance with the project's Data Dictionary.

All drainage breaklines are monotonically enforced to show downhill flow. Water bodies are reviewed in stereo and the lowest elevation is applied to the entire waterbody.

6.2 Breakline Qualitative Assessment

Dewberry completed breakline qualitative assessments according to a defined workflow. The following workflow diagram represents the steps taken by Dewberry to provide a thorough qualitative assessment of the breakline data.



6.3 Breakline Topology Rules

Automated checks are applied to hydro features to validate the 3D connectivity of the feature and the monotonicity of the hydrographic breaklines. Dewberry's major concern was that the hydrographic breaklines have a continuous flow downhill and that breaklines do not undulate. Error points are generated at each vertex not complying with the tested rules and these potential edit calls are then visually validated during the visual evaluation of the data. This step also helped validate that breakline vertices did not have excessive minimum or maximum elevations and that elevations are consistent with adjacent vertex elevations.

The next step is to compare the elevation of the breakline vertices against the elevation extracted from the ESRI Terrain built from the LiDAR ground points, keeping in mind that a discrepancy is expected because of the hydro-enforcement applied to the breaklines and because of the interpolated imagery used to acquire the breaklines. A given tolerance is used to validate if the elevations do not differ too much from the LiDAR.

Dewberry's final check for the breaklines was to perform a full qualitative analysis. Dewberry compared the breaklines against LiDAR intensity images to ensure breaklines were captured in the required locations. The quality control steps taken by Dewberry are outlined in the QA Checklist below.

6.4 Breakline QA/QC Checklist

Project Number/Description: TO 0002 Connecticut LiDAR

Overview

- ☒ All Feature Classes are present in GDB
- ☒ All features have been loaded into the geodatabase correctly. Ensure feature classes with subtypes are domained correctly.
- ☒ The breakline topology inside of the geodatabase has been validated. See Data Dictionary for specific rules
- ☒ Projection/coordinate system of GDB is accurate with project specifications

Perform Completeness check on breaklines using either intensity or ortho imagery

- ☒ Check entire dataset for missing features that were not captured, but should be to meet baseline specifications or for consistency (See Data Dictionary for specific collection rules). NHD data will be used to help evaluate completeness of collected hydrographic features. Features should be collected consistently across tile bounds within a dataset as well as be collected consistently between datasets.
- ☒ Check to make sure breaklines are compiled to correct tile grid boundary and there is full coverage without overlap
- ☒ Check to make sure breaklines are correctly edge-matched to adjoining datasets if applicable. Ensure breaklines from one dataset join breaklines from another dataset that are coded the same and all connecting vertices between the two datasets match in X,Y, and Z (elevation). There should be no breaklines abruptly ending at dataset boundaries and no discrepancies of Z-elevation in overlapping vertices between datasets.

Compare Breakline Z elevations to LiDAR elevations

- ☒ Using a terrain created from LiDAR ground points and water points and GeoFIRM tools, drape breaklines on terrain to compare Z values. Breakline elevations should be at or below the elevations of the immediately surrounding terrain. This should be performed before other breakline checks are completed.

Perform automated data checks using PLTS

The following data checks are performed utilizing ESRI's PLTS extension. These checks allow automated validation of 100% of the data. Error records can either be written to a table for future correction, or browsed for immediate correction. PLTS checks should always be performed on the full dataset.

- ☒ Perform “adjacent vertex elevation change check” on the Inland Ponds feature class (Elevation Difference Tolerance=.001 m). This check will return Waterbodies whose vertices are not all identical. This tool is found under “Z Value Checks.”
- ☒ Perform “unnecessary polygon boundaries check” on Inland Ponds, and Inland Streams feature classes. This tool is found under “Topology Checks.”
- ☒ Perform “duplicate geometry check” on (inland streams to inland streams), (inland ponds to inland ponds), (inland ponds to inland streams). Attributes do not need to be checked during this tool. This tool is found under “Duplicate Geometry Checks.”
- ☒ Perform “geometry on geometry check” on (inland ponds to inland streams). Spatial relationship is contains, attributes do not need to be checked. This tool is found under “Feature on Feature Checks.”
- ☒ Perform “polygon overlap/gap is sliver check” on (inland streams to inland streams), (inland ponds to inland ponds), and (inland ponds to inland streams). Maximum Polygon Area is not required. This tool is found under “Feature on Feature Checks.”

Perform Dewberry Proprietary Tool Checks

- ☒ Perform monotonicity check on inland streams features using “A3_checkMonotonicityStreamLines.” This tool looks at line direction as well as elevation. Features in the output shapefile attributed with a “d” are correct monotonically, but were compiled from low elevation to high elevation. These errors can be ignored. Features in the output shapefile attributed with an “m” are not correct monotonically and need elevations to be corrected. Input features for this tool need to be in a geodatabase. Z tolerance is .01 m. Polygons need to be exported as lines for the monotonicity tool.
- ☒ Perform connectivity check between (inland ponds to inland streams) using the tool “07_CheckConnectivityForHydro.” The input for this tool needs to be in a geodatabase. The output is a shapefile showing the location of overlapping vertices from the polygon features and polyline features that are at different Z-elevation. The unnecessary polygon boundary check must be run and all errors fixed prior to performing connectivity check. If there are exceptions to the polygon boundary rule then that feature class must be checked against itself, i.e. inland streams to inland streams.

Metadata

- ☒ Each XML file (1 per feature class) is error free as determined by the USGS MP tool
- ☒ Metadata content contains sufficient detail and all pertinent information regarding source materials, projections, datums, processing steps, etc. Content should be consistent across all feature classes.

Completion Comments: Complete – Approved



**LiDARgrammetry Data Dictionary
& Stereo Compilation Rules**

For the Connecticut LiDAR Project

August 1, 2012

6.5.1 Horizontal and Vertical Datum

The horizontal datum shall be North American Datum of 1983, Units in meters. The vertical datum shall be referenced to the North American Vertical Datum of 1988 (NAVD 88), Units in meters. Geoid09 shall be used to convert ellipsoidal heights to orthometric heights.

6.5.2 Coordinate System and Projection

All data shall be projected to UTM Zone 18N, Horizontal Units in meters and Vertical Units in meters.

6.5.3 Inland Streams and Rivers

Feature Dataset: BREAKLINES

Feature Type: Polygon

Contains M Values: No

Annotation Subclass: None

XY Resolution: Accept Default Setting

XY Tolerance: 0.003

Feature Class: STREAMS_AND_RIVERS

Contains Z Values: Yes

Z Resolution: Accept Default Setting

Z Tolerance: 0.001

Description

This polygon feature class will depict linear hydrographic features with a width greater than 50 feet.

Table Definition

Field Name	Data Type	Allow Null Values	Default Value	Domain	Precision	Scale	Length	Responsibility
OBJECTID	Object ID							Assigned by Software
SHAPE	Geometry							Assigned by Software
SHAPE_LENGTH	Double	Yes			0	0		Calculated by Software
SHAPE_AREA	Double	Yes			0	0		Calculated by Software

Feature Definition

Description	Definition	Capture Rules
Streams and Rivers	Linear hydrographic features such as streams, rivers, canals, etc. with an average width greater than 50 feet in length. In the case of embankments, if the feature forms a natural dual line channel, then capture it consistent with the capture rules. Other natural or manmade embankments will	Capture features showing dual line (one on each side of the feature). Average width shall be greater than 50 feet to show as a double line. Each vertex placed should maintain vertical integrity and data is required to show "closed polygon". Generally both banks shall be collected to show consistent downhill flow. There are exceptions to this rule where a small branch or offshoot of the stream or river is present. The banks of the stream must be captured at the same elevation to ensure flatness of the water feature. If the elevation of the

	not qualify for this project.	<p>banks appears to be different see the task manager or PM for further guidance.</p> <p>Breaklines must be captured at or just below the elevations of the immediately surrounding terrain. Under no circumstances should a feature be elevated above the surrounding LiDAR points. Acceptable variance in the negative direction will be defined for each project individually.</p> <p>These instructions are only for docks or piers that follow the coastline or water's edge, not for docks or piers that extend perpendicular from the land into the water. If it can be reasonably determined where the edge of water most probably falls, beneath the dock or pier, then the edge of water will be collected at the elevation of the water where it can be directly measured. If there is a clearly-indicated headwall or bulkhead adjacent to the dock or pier and it is evident that the waterline is most probably adjacent to the headwall or bulkhead, then the water line will follow the headwall or bulkhead at the elevation of the water where it can be directly measured. If there is no clear indication of the location of the water's edge beneath the dock or pier, then the edge of water will follow the outer edge of the dock or pier as it is adjacent to the water, at the measured elevation of the water.</p> <p>Every effort should be made to avoid breaking a stream or river into segments.</p> <p>Dual line features shall break at road crossings (culverts). In areas where a bridge is present the dual line feature shall continue through the bridge.</p> <p>Islands: The double line stream shall be captured around an island if the features on either side of the island meet the criteria for capture. In this case a segmented polygon shall be used around the island in order to allow for the island feature to remain as a "hole" in the feature.</p>
--	-------------------------------	---

6.5.4 Inland Ponds and Lakes

Feature Dataset: BREAKLINES

Feature Type: Polygon

Contains M Values: No

Annotation Subclass: None

XY Resolution: Accept Default Setting

XY Tolerance: 0.003

Feature Class: PONDS_AND_LAKES

Contains Z Values: Yes

Z Resolution: Accept Default Setting

Z Tolerance: 0.001

Description

This polygon feature class will depict closed water body features that are at a constant elevation.

Table Definition

Field Name	Data Type	Allow Null Values	Default Value	Domain	Precision	Scale	Length	Responsibility
OBJECTID	Object ID							Assigned by Software
SHAPE	Geometry							Assigned by Software
SHAPE_LENGTH	Double	Yes			0	0		Calculated by Software
SHAPE_AREA	Double	Yes			0	0		Calculated by Software


Feature Definition

Description	Definition	Capture Rules
Ponds and Lakes	<p>Land/Water boundaries of constant elevation water bodies such as lakes, reservoirs, ponds, etc. Features shall be defined as closed polygons and contain an elevation value that reflects the best estimate of the water elevation at the time of data capture. Water body features will be captured for features 2 acres in size or greater.</p> <p>“Donuts” will exist where there are islands within a closed water body feature greater than ½ acre in size.</p>	<p>Water bodies shall be captured as closed polygons with the water feature to the right. <u>The compiler shall take care to ensure that the z-value remains consistent for all vertices placed on the water body.</u></p> <p>Breaklines must be captured at or just below the elevations of the immediately surrounding terrain. Under no circumstances should a feature be elevated above the surrounding LiDAR points. Acceptable variance in the negative direction will be defined for each project individually.</p> <p>An Island within a Closed Water Body Feature will also have a “donut polygon” compiled.</p> <p>These instructions are only for docks or piers that follow the coastline or water’s edge, not for docks or piers that extend perpendicular from the land into the water. If it can be reasonably determined where the edge of water most probably falls, beneath the dock or pier, then the edge of water will be collected at the elevation of the water where it can be directly measured. If there is a clearly-indicated headwall or bulkhead adjacent to the dock or pier and it is evident that the waterline is most probably adjacent to the headwall or bulkhead, then the water line will follow the headwall or bulkhead at the elevation of the water where it can be directly measured. If there is no clear indication of the location of the water’s edge beneath the dock or pier, then the edge of water will follow the outer edge of the dock or pier as it is adjacent to the water, at the measured elevation of the water.</p>

7 DEM Production & Qualitative Assessment

7.1

Dewberry Hydro-Flattening Workflow



DEM Production Methodology

Dewberry's utilizes ESRI software and Global Mapper for the DEM production and QC process. ArcGIS software is used to generate the products and the QC is performed in both ArcGIS and Global Mapper.

1. Generate LiDAR Stereo Pairs using GeoCue: Create stereo pairs with the raster pixel size being equal to the nominal point spacing. Stereo pairs will be created for Bare-Earth and Full-Point Cloud.
2. Extract Breaklines: Breaklines will be extracted according to the data dictionary outlined on the previous pages.
3. Classify Water Points: LAS point falling within hydrographic breaklines shall be classified to ASPRS class 9 using TerraScan. Breaklines must be prepared correctly prior to performing this task.

4. Classify Ignored Ground Points: Points within a specified distance of breaklines can be removed from the ground classification and re-classified to a separate class, usually class 10. Ignored ground points were not created for the Connecticut LiDAR project.
5. Terrain Processing: A Terrain will be generated using the Breaklines and LAS data that has been imported into Arc as a Multipoint File. If the final DEMs are to be clipped to a project boundary that boundary will be used during the generation of the Terrain.
6. Create DEM Zones for Processing: Create DEM Zones that are buffered by 2 tiles around the edges. Zones should be created in a logical manner to minimize the number of zones without creating zones too large for processing. Dewberry will make zones no larger than 200 square miles (taking into account that a DEM will fill in the entire extent not just where LiDAR is present). Once the first zone is created it must be verified against the tile grid to ensure that the cells line up perfectly with the tile grid edge.
7. Convert Terrain to Raster: Convert Terrain to raster using the DEM Zones created in step 6. In the environmental properties set the extents of the raster to the buffered Zone. For each subsequent zone, the first DEM will be utilized as the snap raster to ensure that zones consistently snap to one another.
8. Perform Initial QA/QC on Zones: During the initial QA process anomalies will be identified and corrective polygons will be created.
9. Correct Issues on Zones: Corrections on zones will be performed following Dewberry's in-house correction process.
10. Extract Individual Tiles: Individual Tiles will be extracted from the zones utilizing a Dewberry proprietary tool.
11. Final QA: Final QA will be performed on the dataset to ensure that tile boundaries are seamless.

7.2 DEM Qualitative Assessment

Dewberry performed a comprehensive qualitative assessment of the DEM deliverables to ensure that all tiled DEM products were delivered with the proper extents, were free of processing artifacts, and contained the proper referencing information. This process was performed in ArcGIS software with the use of a tool set Dewberry has developed to verify that the raster extents match those of the tile grid and contain the correct projection information. The DEM data was reviewed at a scale of 1:8000 to review for artifacts caused by the DEM generation process and to review the hydro-flattened features. Dewberry uses Global Mapper to perform this review. Corrections are applied in Arc Map. Dewberry creates HillShade models and overlays a partially transparent colorized elevation model in order to perform the corrections. The last step is to load the DEM data into Global Mapper to ensure that the corrections are acceptable, all files are readable, and that no artifacts exist between tiles. The figure below, illustrates the detail of the final DEMs and how the DEMs display elevation changes within hydrographic features.

7.3 DEM QA/QC Checklist

Project Number/Description: TO 00002 Connecticut LiDAR

Overview



- Correct number of files is delivered and all files are in ESRI GRID format
- Verify Raster Extents

- ☒ Verify Projection/Coordinate System

Review

- ☒ Manually review bare-earth DEMs with a hillshade to check for issues with hydro-flattening process or any general anomalies that may be present. Specifically, water should be flowing downhill, water features should NOT be floating above surrounding terrain and bridges should NOT be present in bare-earth DEM. Hydrologic breaklines should be overlaid during review of DEMs.
- ☒ DEM cell size is 1 meter
- ☒ Perform final overview in Global Mapper to ensure seamless product.

Metadata

- ☒ Project level DEM metadata XML file is error free as determined by the USGS MP tool
- ☒ Metadata content contains sufficient detail and all pertinent information regarding source materials, projections, datums, processing steps, etc.

Completion Comments: **Complete - Approved**